



ZONING / SUBDIVISION MAP


DESIGN ADHERES TO CODES LISTED BELOW:
2015 INTERNATIONAL BUILDING CODE
2015 INTERNATIONAL MECHANICAL CODE
2015 INTERNATIONAL PLUMBING CODE
2015 INTERNATIONAL FIRE CODE
2015 INTERNATIONAL ENERGY CONSERVATION CODE

BANDERA RETAIL CENTER
7706 BANDERA RD
SAN ANTONIO, TX 78238

CLIENT
BANDERA PARTNERS, LLC
12300 W INTERSTAE 10, SAN ANTONIO, TX 77084
(210) 422-7500

CONSULTING ENGINEERS
PROFESSIONAL StruCIVIL ENGINEERS
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD, SUITE 390, AUSTIN, TX 78759
(512) 238-6422 PSCE@PSCEINC.COM

- LIST OF DRAWINGS
- 1. COVER SHEET
 - 2. FINAL PLAT
 - 3. EXISTING SURVEY
 - 4. DIMENSIONAL SITE PLAN
 - 5. GRADING SITE PLAN
 - 6. ON-SITE DRAINAGE AREA MAP
 - 7. EROSION SEDIMENTATION CONTROL PLAN
 - 8. UTILITY SITE PLAN
 - 9. FIRE LANE & EMERGENCY ACCESS PLAN
 - 10. GENERAL DETAILS
 - 11. GENERAL DETAILS
 - 12. GENERAL DETAILS
 - 13. GENERAL DETAILS
 - 14. GENERAL DETAILS
 - 15. GENERAL DETAILS
 - 16. GENERAL DETAILS
 - 17. IRRIGATION PLAN
 - 18. IRRIGATION DETAILS
 - 19. IRRIGATION DETAILS
 - 20. LANDSCAPE PLAN
 - 21. LANDSCAPE DETAILS
 - 22. LANDSCAPING SPECIFICATIONS
 - 23. LANDSCAPING SPECIFICATIONS
 - 24. LANDSCAPING SPECIFICATIONS
 - 25. LANDSCAPING SPECIFICATIONS



SITE LOCATION MAP

SUBMITTAL DATE	
PROJECT TITLE	BANDERA RETAIL CENTER
STREET ADDRESS	7706 BANDERA ROAD, SAN ANTONIO, TX 78148
PROPERTY OWNER	BANDERA PARTNERS, LLC 12300 W INTERSTATE 10, SAN ANTONIO, TX 78230 CONTACT: BIJAN BONAKCHI (210)-422-7500
ARCHITECT	TCHEN ARCHITECTS 11908 ANDERSON MILL, SUITE 325, AUSTIN, TX 78726 CONTACT: (512)-351-1801
DESIGN COMPANY	PROFESSIONAL STRUCIVIL ENGINEERS, INC. 12710 RESEARCH BLVD., SUITE 390, AUSTIN, TX 78759 CONTACT: MIRZA TAHIR BAIG (512) 238-6422 1904 FORTVIEW ROAD, AUSTIN, TX 78704
LANDSCAPE ARCHITECT	PLACE MATRIX DESIGN OFFICE PO BOX 41107, AUSTIN, TX 78704 CONTACT: (512)-599-4095
SURVEYOR	TRUE LINE CONSTRUCTION LAYOUT LLC 9918 MCCULLOUGH AVE., SAN ANTONIO, TX 78246 (210)-663-7208
NAME OF WATERSHED	UPPER LEON CREEK
100-YEAR FLOOD PLAIN	NO PORTION OF THE PROPERTY DESCRIBED HEREON IS LOCATED IN ZONE "X" AS SHOWN ON THE FEDERAL INSURANCE ADMINISTRATION FLOOD HAZARD BOUNDARY MAP, PANEL NO. 480035 0220 G, DATED: SEPTEMBER 29, 2010.
LEGAL DESCRIPTION	NCB 17973 BLK 12 LOT 2 (BANDERA HEIGHTS SUBD), RECORDED IN BEXAR COUNTY, TEXAS.

APPROVED BY:	DATE:
SAN ANTONIO WATER SYSTEM	
REVIEWED BY:	DATE:
CITY OF SAN ANTONIO	
APPROVED BY:	DATE:
FIRE DEPARTMENT	
UTILITY PROVIDER:	
1) WATER IS PROVIDED BY SAN ANTONIO WATER SYSTEM.	
2) WASTEWATER IS PROVIDED BY SAN ANTONIO WATER SYSTEM.	



San Antonio
Design Group Inc.
CONSULTING ENGINEERS
3401 LUCKWILL BLVD. SUITE 210
SAN ANTONIO, TEXAS 78201
PH: (210) 342-4000 FAX: (210) 342-4001

OWNER/DEVELOPER:
DIPLOMAT CAPITAL M.G. LTD.
3834 FREDERICKSBURG ROAD
SAN ANTONIO, TEXAS 78201
(210) 641-0400

PROJECTS
SITE
LOCATION MAP
NOT TO SCALE

LINE	LENGTH	BEARING
L1	50.10	S74°48'36"W
L2	18.83	S89°15'13"W
L3	121.30	N32°27'44"W
L4	84.86	N51°15'25"W
L5	58.00	S73°30'22"W
L6	138.87	N57°12'22"W
L7	22.16	N32°01'59"W
L8	59.57	N09°31'00"W
L9	28.11	S26°21'19"W
L10	59.24	N81°14'38"W
L11	42.01	N86°07'56"W
L12	41.65	N77°29'13"W
L13	110.10	S73°02'15"W
L14	24.51	S88°24'10"W
L15	37.88	N34°12'35"W
L16	50.00	N18°00'07"W
L17	64.82	N44°13'42"W
L18	35.12	N09°04'55"W
L19	38.63	N52°19'58"W
L20	29.86	N37°17'07"W
L21	70.80	N67°14'44"W
L22	45.12	N60°08'18"W
L23	73.90	N10°23'50"W
L24	24.66	N07°46'23"W

NOTES:
1. MONITORING OR CONTROL INFORMATION AVAILABLE AT THE OFFICE OF SAN ANTONIO DESIGN GROUP, INC.
2. BASIS OF BEARINGS FOR THIS PLAT: NAD 83 TEXAS STATE PLANE COORDINATES.
3. 1/2" HIGH ROD SET AT ALL CORNERS UNLESS OTHERWISE NOTED.
4. COORDINATES SHOWN BASED ON NAD 83 TEXAS STATE PLANE COORDINATES.
5. THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELEC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED BELOW.
6. THE CHANGING LOCATION OF THE SUBJECT TRACT ON THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) FLOOD INSURANCE RATE MAP COMMUNITY PANEL NO. 48029-00246, EFFECTIVE DATE JANUARY 4, 2002, INDICATES THAT THE SUBJECT TRACT IS LOCATED WITHIN ZONE "X" (SH-3) WHICH IS SURFACED BY FEMA AS AREAS DETERMINED TO BE OUTSIDE 100-YEAR FLOOD PLAIN. THIS STATEMENT DOES NOT IMPLY THAT THE SUBJECT TRACT IS TOTALLY FLOOD FREE OF POTENTIAL FLOODING. LOCALIZED FLOODING CAN OCCUR DUE TO NATURAL AND/OR MANMADE INFLUENCES. THIS FLOOD STATEMENT SHALL NOT CREATE ANY LIABILITY ON THE PART OF SAN ANTONIO DESIGN GROUP, INC. OR THE UNDERSIGNED.
7. WILL COMPLY WITH THE STREET SCOPE STANDARDS 33-512 DURING THE BUILDING PERMIT PHASE.
8. OWNER SHALL PROVIDE FOR SHARED CROSS ACCESS WITH ADJACENT LOTS IN COMPLIANCE WITH U.D.C. SECTION 33-504.
9. FINISHED FLOOR ELEVATION MUST BE A MINIMUM OF 8 INCHES ABOVE FINAL ADJACENT GROUND.

EDU NOTE:
THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDU'S) FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE AT THE SAN ANTONIO DEVELOPMENT SERVICES DEPARTMENT.

A) NO STRUCTURES, FENCES, WALLS OR OBSTRUCTIONS OF ANY KIND SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENT OR R.O.W. SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPES OF MODIFICATIONS WHICH ALTER THE CROSS SECTIONS OF THE DRAINAGE EASEMENT AS APPROVED SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEAR COUNTY SHALL HAVE THE RIGHT OF ACCESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENT AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENT.

B) MINIMUM FINISHED FLOOR ELEVATIONS FOR RESIDENTIAL AND COMMERCIAL LOTS SHALL BE ELEVATED AT LEAST 1 FOOT HIGHER THAN THE COMPUTED WATER SURFACE ELEVATION FOR THE 100 YEAR ULTIMATE DEVELOPMENT FLOOD.

THOUGHT NOTES:
(1) FOR RESIDENTIAL DEVELOPMENT DIRECTLY ADJACENT TO STATE RIGHT-OF-WAY, THE DEVELOPER SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE SIDEWALK AND/OR SOUND ABATEMENT MEASURES FOR FUTURE NOISE MITIGATION.
(2) OWNER/DEVELOPER IS RESPONSIBLE FOR PREVENTING ANY ADVERSE IMPACT TO THE EXISTING DRAINAGE SYSTEM WITHIN THE HIGHWAY RIGHT-OF-WAY.
(3) MAXIMUM ACCESS POINTS TO STATE HIGHWAY FROM THIS PROPERTY WILL BE RECALCULATED AS DIRECTED BY REGULATIONS FOR ACCESS DRIVEWAYS TO STATE HIGHWAYS. THIS PROPERTY IS ELIGIBLE FOR A MAXIMUM COMBINED TOTAL OF ONE ACCESS POINT ALONG SH 16, BASED ON OVERALL PLATTED HIGHWAY FRONTAGE OF 417.46.
(4) IF SIDEWALKS ARE REQUIRED BY APPROPRIATE CITY ORDINANCE, A SIDEWALK PERMIT MUST BE APPROVED BY THOUGHT PRIOR TO CONSTRUCTION WITHIN STATE RIGHT-OF-WAY. LOCATIONS OF SIDEWALKS WITHIN STATE RIGHT-OF-WAY SHALL BE DIRECTED BY THOUGHT.



CURVE	RADIUS	LENGTH	TANGENT	DELTA	CHORD	CHORD BEARING
C1	570.00'	205.01'	103.62'	20°34'25"	203.90'	S47°36'17"W
C2	1228.00'	92.65'	46.33'	04°19'21"	92.63'	S60°04'57"W
C3	1228.00'	92.65'	46.33'	04°19'21"	92.62'	S60°04'58"W
C4	15.00'	23.46'	14.82'	89°41'03"	21.16'	N77°16'18"W

SUBDIVISION PLAT ESTABLISHING
BANDERA HEIGHTS SUBDIVISION

BEING A TOTAL OF 5.04 ACRES OF LAND IN THE CITY OF SAN ANTONIO, BLOCK LOT P-113 (3.82AC), P-109 (.344AC), & P-110 (.872AC), N.C.B. 17973 AS DESCRIBED BY DEED RECORDED IN VOLUME 10395 PAGE 0433 BEING OF THE OFFICIAL PUBLIC RECORDS OF BEAR COUNTY, TEXAS, ESTABLISHING LOT 1, LOT 2, AND LOT 3, BLOCK 12, NEW CITY BLOCK 17973 SAN ANTONIO, TEXAS: BEAR COUNTY PLAT RECORDS.

PLAT NUMBER: 080296

STATE OF TEXAS
COUNTY OF BEAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATED TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

[Signature]
BY:

DULY AUTHORIZED AGENT

STATE OF TEXAS
COUNTY OF BEAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED MIRZA TAHR BAIG, P.E., #82577 ON 04/20/2018, FIRM REGISTRATION T-4851, WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 29th day of July, A.D. 2008.
[Signature]
J. A. SANCHEZ JR.
Notary Public
State of Texas
Comm. exp 05-06-2011

STATE OF TEXAS
COUNTY OF BEAR

I HEREBY CERTIFY THAT THE PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF ERECTS, LOTS AND DRAINAGE LAYOUT, TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.



STATE OF TEXAS
COUNTY OF BEAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY: HENRY A. KUEHLEN, R.L.S.



THE CITY OF SAN ANTONIO AS A PART OF ITS ELECTRIC AND GAS SYSTEM (CITY PUBLIC SERVICE) HAS HERETOFORE DESIGNATED THE EASEMENTS AND RIGHT-OF-WAY FOR ELECTRIC AND GAS DISTRIBUTION AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THE PLAT AS ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE, AND TRUCKING RIGHT-OF-WAY. THE CITY OF SAN ANTONIO HEREBY AGREES TO MAINTAIN AND PROTECT THE EASEMENTS AND RIGHT-OF-WAY FOR ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE, AND TRUCKING RIGHT-OF-WAY. THE CITY OF SAN ANTONIO HEREBY AGREES TO MAINTAIN AND PROTECT THE EASEMENTS AND RIGHT-OF-WAY FOR ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE, AND TRUCKING RIGHT-OF-WAY. THE CITY OF SAN ANTONIO HEREBY AGREES TO MAINTAIN AND PROTECT THE EASEMENTS AND RIGHT-OF-WAY FOR ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE, AND TRUCKING RIGHT-OF-WAY.

THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELEC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED BELOW.

ALL EXISTING FACILITIES TO BE MAINTAINED OR ABANDONED IN PLACE, NEW FACILITIES TO BE INSTALLED IN ACCORDANCE WITH NEW LOT SCHEDULE.

THIS PLAT OF BANDERA HEIGHTS SUBDIVISION HAS BEEN SUBMITTED TO THE CITY OF SAN ANTONIO, TEXAS, AND HAVING BEEN REVIEWED BY THE DIRECTOR OF DEVELOPMENT SERVICES, IS HEREBY APPROVED IN ACCORDANCE WITH STATE AND LOCAL LAWS AND REGULATIONS AS INDICATED BELOW.

MAKING ON ANY OTHER PLAT APPROVED BY THE DIRECTOR OF DEVELOPMENT SERVICES, DATED THIS 18th day of April, A.D. 2008.
[Signature]
DIRECTOR OF DEVELOPMENT SERVICES
STATE OF TEXAS
COUNTY OF BEAR
I, *[Signature]*, COUNTY CLERK OF SAID COUNTY, DO HEREBY CERTIFY THAT THIS PLAT WAS FILED FOR RECORD IN MY OFFICE, ON THE 18th day of April, A.D. 2008, AT 1:22 PM, AND DULY RECORDED THE 18th day of April, A.D. 2008, IN THE RECORDS OF DEEDS, & PLAT OF SAID COUNTY, IN BOOK VOLUME 4941 ON PAGE 211. IN TESTIMONY WHEREOF, I WITNESS MY HAND AND OFFICIAL SEAL OF OFFICE, THIS 18th day of April, A.D. 2008.
COUNTY CLERK, BEAR COUNTY, TEXAS
[Signature], DEPUTY


THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHR BAIG, P.E., #82577 ON 04/20/2018, FIRM REGISTRATION T-4851.

Project: BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

30434

2 OF 25

FINAL PLAT



SCALE: 1"=40'

CURVE	RADIUS	ARC LENGTH	CHORD LENGTH	CHORD BEARING	DELTA ANGLE
C1	1228.06'	50.23' (50.10')	50.23'	S 60°54'32" W	2°20'37"
C2	1228.06'	92.52' (92.65')	92.50'	S 60°12'21" W	4°18'59"
C3	15.00'	23.35' (23.48')	21.06'	N 77°26'30" W	89°11'48"
LINE BEARING DISTANCE					
L1	S 57°44'47" W 49.90'				
	(S 57°51'13" W) (49.93')				
L2	N 32°34'10" W 121.38'				
	(N 32°27'44" W)				
L3	N 23°47'07" W 89.82'				
	(N 23°40'41" W)				

THIS PROPERTY IS NOT SUBJECT TO THE ELECTRIC TRANSMISSION LINE EASEMENT RECORDED IN VOLUME 1077, PAGE 311, DEED RECORDS, BEXAR COUNTY, TEXAS.

THIS PROPERTY IS NOT SUBJECT TO THE SANITARY SEWER EASEMENT RECORDED IN VOLUME 7513, PAGE 728, DEED RECORDS, BEXAR COUNTY, TEXAS.

THIS PROPERTY IS NOT SUBJECT TO INGRESS AND EGRESS EASEMENT RECORDED IN VOLUME 2446, PAGE 1924, OFFICIAL PUBLIC RECORDS, BEXAR COUNTY, TEXAS.

NOTE: Bearings shown hereon are based on actual GPS Observations, Texas State Plane Coordinates, South Central Zone, Grid.

THIS PROPERTY IS SUBJECT TO RESTRICTIVE COVENANTS, EASEMENTS, AGREEMENTS, AND/OR SETBACK LINES (IF ANY) AS FOLLOWS: VOLUME 9594, PAGE 211, DEED AND PLAT RECORDS; VOLUME 14700, PAGE 340, OFFICIAL PUBLIC RECORDS, BEXAR COUNTY, TEXAS.

NOTE: PRIOR SURVEY (WESTAR JOB #80572) WAS USED FOR REFERENCE.

THIS SURVEY IS ACKNOWLEDGED AND IS ACCEPTED:

FIRM REGISTRATION NO. 1011700

Westar Alamo

LAND SURVEYORS, L.L.C.

P.O. BOX 1645 BOERNE, TEXAS 78008
PHONE (210) 372-9500 FAX (210) 372-9999

G.F. NO. 2293150-SA68

LEGEND

- ▲ CALCULATED POINT
- FIND 1/2" IRON ROD
- RECORD INFORMATION
- BUILDING SETBACK
- RECORD DENSITY MONUMENT
- POWER POLE
- ▲ FIND MAG NAIL
- CABLE TELEVISION
- TELEPHONE CABLE
- UNDERGROUND CABLE
- ELECTRIC BOX
- OVERHEAD ELECTRIC
- GUY WIRE
- SEWER MANHOLE
- LIGHT POST

DRAWN BY: BLE/TJS

JOB NO. 80806

FLOOD ZONE INTERPRETATION: IT IS THE RESPONSIBILITY OF ANY INTERESTED PERSONS TO VERIFY THE ACCURACY OF FEMA FLOOD ZONE DESIGNATION OF THIS PROPERTY WITH FEMA AND STATE AND LOCAL OFFICIALS, AND TO DETERMINE THE EFFECT THAT SUCH DESIGNATION MAY HAVE REGARDING THE INTENDED USE OF THE PROPERTY. The property made the subject of this survey appears to be included in a FEMA Flood Insurance Rate Map (FIRM), identified as Community No. 48029C, Panel No. 0220 G, which is Dated 06/29/2010. By scaling from that FIRM, it appears that all or a portion of the property may be in Flood Zone(s) XAE. Because this is a boundary survey, the surveyor did not take any action to determine the Flood Zone status of the surveyed property other than to interpret the information set out on FEMA's FIRM as described above. THIS SURVEYOR DOES NOT CERTIFY THE ACCURACY OF THIS INTERPRETATION OF THE FLOOD ZONES, which may not agree with the interpretations of FEMA or State or local officials, and which may not agree with the tract's actual conditions. More information concerning FEMA's Special Flood Hazard Areas and Zones may be found at <http://www.fema.gov/index.shtml>.

Property Address:
7800 BANDERA ROAD
Property Description:
LOT 2, BLOCK 12, NEW CITY BLOCK 17973, BANDERA HEIGHTS SUBDIVISION, CITY OF SAN ANTONIO, BEXAR COUNTY, TEXAS, ACCORDING TO MAP OR PLAT THEREOF RECORDED IN VOLUME 9594, PAGE 211 OF THE DEED AND PLAT RECORDS OF BEXAR COUNTY, TEXAS.

Owner:
DARIO PROPERTIES, LTD.

I, MARK J. EWALD, Registered Professional Land Surveyor, State of Texas, do hereby certify that the above plat represents an actual survey made on the ground under my supervision, and there are no discrepancies, conflicts, shortages in area or boundary lines, or any encroachment or overlapping of improvements, to the best of my knowledge and belief, except as shown herein.

MARK J. EWALD
Registered Professional Land Surveyor
Texas Registration No. 5095

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHIR BAG, P.E., #82577 ON 04/30/2019
FIRM REGISTRATION F-4951

Project: BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Title: EXISTING SURVEY

30434



3 OF 25

EROSION CONTROL LEGEND

	TREE (EXISTING)
	TREE (TO BE REMOVED) (R)
	TREE PROTECTION

SUMMARY OF PARKING SPACES
PROVIDED STANDARD SPACES
PROVIDED HANDICAP VAN
PROVIDED STANDARD HANDICAP
PROVIDED LOADING SPACE

CONTRACTOR TO CHECK
BACK OF PLANS
COSA TRAFFIC NOTES



TEXAS DOT JURISDICTION
STATE PERMITS REQUIRED
ON ALL STATE R.O.W.

BANDERA ROAD (S.H.16)
(VARIABLE WIDTH R.O.W.)

ELECTRIC, TELEPHONE, GAS, ANCHOR, SERVICE, OVERHANG
UTILITY, AND TRANSFORMER EASEMENT

0 20 40
GRAPHIC SCALE 1"=20'-0"

5-0
DEVELOPMENT SERVICES DEPARTMENT
TRAFFIC REVIEW SECTION
SCHEDULE CONSTRUCTION INSPECTIONS
24 HOURS IN ADVANCE AT 207-1111

PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS





Project : **BANDERA RETAIL CENTER**
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

title: **THREE-DIMENSIONAL SITE PLAN**

PROJECT
30434

4

GENERAL LEGEND	
	PROPERTY LINE
	LIMITS OF CONSTRUCTION
	SILT FENCE & LOC
	PUBLIC UTILITY EASEMENT
	DRAINAGE EASEMENT
	ELECTRICAL EASEMENT
	SANITARY SEWER EASEMENT
	WATER SURFACE ELEVATION
	CORRUGATED METAL PIPE
	EXISTING CONTOURS
	PROPOSED GRADING CONTOURS
UTILITY LEGEND	
	FIRE HYDRANT
	GATE VALVE
	PLUG OR CAP
	STORM SEWER MANHOLE
	WASTEWATER MANHOLE
	WW CLEAN-OUT
	WATER LINE
	WASTEWATER LINE
	STORM SEWER LINE
	FLOW INDICATOR (SHOWN TO RIGHT)
	PROPOSED SERVICE TAP
	WATER METER
	IRRIGATION METER
	STORM SEWER INLET
	WATER SERVICE (SINGLE)
	WATER SERVICE (DOUBLE)
	UTILITY POLE
	LIGHT POLE
	OVERHEAD ELECTRIC
	WIRE FENCE
EROSION CONTROL LEGEND	
	TREE (EXISTING)
	TREE (TO BE REMOVED) (R)
	TREE PROTECTION



THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHIR BAIG, P.E., #82577 ON 10/01/2018 FIRM REGISTRATION F-4951


Rev.	Date	Description
1	10/07/18	ISSUED FOR APPROVAL
2	09/10/18	ISSUED FOR APPROVAL
3	05/07/18	ISSUED FOR APPROVAL

PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78759 | TEL: 512.228.6422 | FAX: 512.228.8996


Project: **BANDERA RETAIL CENTER**
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Title: **GRADING SITE PLAN**

30434



PRE DEVELOPED CONDITIONS



POST DEVELOPED CONDITIONS

DRAINAGE SUMMARY TABLE (PRE & POST CONDITIONS)						
BASIN NAME	PRE DA#1	POST DA#1	POST DA#2	TOTAL PRE "Q"	TOTAL POST "Q"	TOTAL POST "Q" RELEASE
DRAINAGE AREA (acres)	1.07	0.403	0.667			
IMPERVIOUS COVER (acres)	0.00	0.386	0.356			
CN	79	97	89			
CN (adjusted)	79	96.47	92.60			
Tc (hrs.)	0.177	0.083	0.083			
5YRS. (cfs)	2.14	1.41	2.02	2.14	3.44	3.44
25YRS. (cfs)	5.07	2.59	4.04	5.07	6.63	6.63
100YRS. (cfs)	7.31	3.46	5.53	7.31	8.99	8.99

Project: **BANDERA RETAIL CENTER**
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Sheet: **30434**

Scale: **1"=40'**

ON-SITE DRAINAGE AREA MAP




6 OF 25

Professional Engineer's Seal: **MIRZA TAHR BAG**, P.E., #02577
Firm Registration: F-4951

Professional Engineer's Seal: **PROFESSIONAL STRUCTURAL ENGINEERS, INC.**
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78758 | TEL: 512.238.6022 | FAX: 512.238.8058

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHR BAG, P.E., #02577 ON 10/01/2018

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHR BAG, P.E., #02577 ON 10/01/2018

[illegible]

PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS

Project : **BANDERA RETAIL CENTER**
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Title : **EROSION/SEDIMENTATION SITE PLAN**

PROJECT

30434

P

E

P

7

DEPARTMENT SIGNATURE

SAWS CONSTRUCTION NOTES
COUNTER PERMIT AND GENERAL CONSTRUCTION PERMIT

GENERAL SECTION


- ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF THIS CONTRACT SHALL BE APPROVED BY THE SAN ANTONIO WATER SYSTEM (SAWS) AND COMPLY WITH THE PLANS, SPECIFICATIONS, GENERAL CONDITIONS AND WITH THE FOLLOWING AS APPLICABLE:
 - CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) DESIGN CRITERIA FOR DOMESTIC WASTEWATER SYSTEM, TEXAS ADMINISTRATIVE CODE (TAC) TITLE 30 PART 1 CHAPTER 217 AND "PUBLIC DRINKING WATER", TAC TITLE 30 PART 1 CHAPTER 290.
 - CURRENT TCEQ "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS, STREETS AND DRAINAGE".
 - CURRENT "SAN ANTONIO WATER SYSTEM STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION".
 - CURRENT CITY OF SAN ANTONIO "STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION".
 - CURRENT CITY OF SAN ANTONIO "UTILITY EXCAVATION CRITERIA MANUAL" (UECM).
- THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE APPROVED COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP) FROM THE CONSULTANT AND HAS BEEN NOTIFIED BY SAWS CONSTRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE WORK REQUIREMENTS, WORK COMPLETED BY THE CONTRACTOR WITHOUT AN APPROVED COUNTER PERMIT AND/OR A GCP WILL BE SUBJECT TO REMOVAL AND REPLACEMENT AT THE EXPENSE OF THE CONTRACTORS AND/OR THE DEVELOPER.
- THE CONTRACTOR SHALL OBTAIN THE SAWS STANDARD DETAILS FROM THE SAWS WEBSITE, [HTTP://WWW.SAWS.ORG/BUSINESS_CENTER/SPECS](http://www.saws.org/BUSINESS_CENTER/SPECS), UNLESS OTHERWISE NOTED WITHIN THE DESIGN PLANS.
- THE CONTRACTOR IS TO MAKE ARRANGEMENTS WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973, ON NOTIFICATION PROCEDURES THAT WILL BE USED TO NOTIFY AFFECTED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO BEGINNING ANY WORK.
- LOCATION AND DEPTH OF EXISTING UTILITIES AND SERVICE LATERALS SHOWN ON THE PLANS ARE UNDERSTOOD TO BE APPROXIMATE. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT LEAST 1 WEEK PRIOR TO CONSTRUCTION. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION AT NO COST TO SAWS.
- THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 1-2 WEEKS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT. PLEASE ALLOW UP TO 7 BUSINESS DAYS FOR LOCATES REQUESTING PIPE LOCATION MARKERS ON SAWS FACILITIES. THE FOLLOWING CONTACT INFORMATION ARE SUPPLIED FOR VERIFICATION PURPOSES:
 - SAWS UTILITY LOCATES: [HTTP://WWW.SAWS.ORG/SERVICE/LOCATES](http://www.saws.org/SERVICE/LOCATES)
 - COSA DRAINAGE (210) 207-0724 OR (210) 207-6026
 - COSA TRAFFIC SIGNAL OPERATIONS (210) 206-8480
 - COSA TRAFFIC SIGNAL DAMAGES (210) 207-3951
 - TEXAS STATE WIDE ONE CALL LOCATOR 1-800-545-6005 OR 811
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES TO ITS ORIGINAL OR BETTER CONDITION IF DAMAGES ARE MADE AS A RESULT OF THE PROJECT'S CONSTRUCTION.
- ALL WORK IN TEXAS DEPARTMENT OF TRANSPORTATION (TxDOT) AND/OR BEXAR COUNTY RIGHT-OF-WAY SHALL BE DONE IN ACCORDANCE WITH RESPECTIVE CONSTRUCTION SPECIFICATIONS AND PERMIT REQUIREMENTS.
- THE CONTRACTOR SHALL COMPLY WITH CITY OF SAN ANTONIO OR OTHER GOVERNING MUNICIPALITY'S TREE ORDINANCES WHEN EXCAVATING NEAR TREES.
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100'-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- HOLIDAY WORK: CONTRACTORS WILL NOT BE ALLOWED TO PERFORM SAWS WORK ON SAWS RECOGNIZED HOLIDAYS. REQUEST SHOULD BE SENT TO CONSTRUCTION@SAWS.ORG.
- WEEKEND WORK: CONTRACTORS ARE REQUIRED TO NOTIFY THE SAWS INSPECTION CONSTRUCTION DEPARTMENT 48 HOURS IN ADVANCE TO REQUEST WEEKEND WORK. REQUEST SHOULD BE SENT TO CONSTRUCTION@SAWS.ORG.
- ANY AND ALL SAWS UTILITY WORK INSTALLED WITHOUT HOLIDAY/WEEKEND APPROVAL WILL BE SUBJECT TO BE UNCOVERED FOR PROPER INSPECTION.
- COMPACTION NOTE (ITEM 804): THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING THE COMPACTION REQUIREMENTS ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE SAWS INSPECTOR AND/OR THE TEST ADMINISTRATOR, PER EACH 12-INCH DEEP LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.
- A COPY OF ALL TESTING REPORTS SHALL BE FORWARDED TO SAWS CONSTRUCTION INSPECTION DIVISION.

WATER SECTION

- PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
 - FOR WATER MAINS 12" OR HIGHER: SAWS EMERGENCY OPERATIONS CENTER (210) 233-2014
- ASBESTOS CEMENT (AC) PIPE, ALSO KNOWN AS TRANSITE PIPE WHICH IS KNOWN TO CONTAIN ASBESTOS- CONTAINING MATERIAL (ACM), MAY BE LOCATED WITHIN THE PROJECT LIMITS. SPECIAL WASTE MANAGEMENT PROCEDURES AND HEALTH AND SAFETY REQUIREMENTS WILL BE APPLICABLE WHEN REMOVAL AND/OR DISTURBANCE OF THIS PIPE OCCURS. SUCH WORK IS TO BE MADE UNDER SPECIAL SPECIFICATION ITEM NO. 3000, "SPECIAL SPECIFICATION FOR HANDLING ASBESTOS CEMENT PIPE".
- VALVE REMOVAL: WHERE THE CONTRACTOR IS TO ABANDON A WATER MAIN, THE CONTROL VALVE LOCATED ON THE ABANDONING BRANCH WILL BE REMOVED AND REPLACED WITH A CAP/PLUG (NPT).
- SUITABLE ANCHORAGE/THROST BLOCKING OR JOINT RESTRAINT SHALL BE PROVIDED AT ALL OF THE FOLLOWING MAIN LOCATIONS: DEAD ENDS, PLUGS, CAPS, TEES, CROSSES, VALVES, AND BENDS, IN ACCORDANCE WITH THE STANDARD DRAWINGS DD-830 SERIES AND ITEM NO. 830, IN THE SAWS STANDARD SPECIFICATIONS FOR CONSTRUCTION.
- ALL VALVES SHALL READ "OPEN RIGHT".
- PRVS REQUIRED: CONTRACTOR TO VERIFY THAT NO PORTION OF THE TRACT IS BELOW GROUND ELEVATION OF 849.0 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS WHERE THE GROUND LEVEL IS BELOW 849.0 EET, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO. NO DUAL SERVICES ALLOWED FOR ANY LOT(S) IF *PRV IS/ARE REQUIRED FOR SUCH LOT(S), ONLY SINGLE SERVICE CONNECTIONS SHALL BE ALLOWED. *NOTE: A PRESSURE REGULATOR IS ALSO KNOWN AS A PRESSURE REDUCING VALVE (PRV).
- PIPE DISINFECTION WITH DRY HYD FOR PROJECTS LESS THAN 800 LINEAR FEET, (ITEM NO. 847.3): MAINS SHALL BE DISINFECTED WITH DRY HYD WHERE SHOWN IN THE CONTRACT DOCUMENTS OR AS DIRECTED BY THE INSPECTOR, AND SHALL NOT EXCEED A TOTAL LENGTH OF 800 FEET. THIS METHOD OF DISINFECTION WILL ALSO BE FOLLOWED FOR MAIN REPAIRS. THE CONTRACTOR SHALL UTILIZE ALL APPROPRIATE SAFETY MEASURE TO PROTECT HIS PERSONNEL DURING DISINFECTION OPERATIONS.
- BACKFLOW PREVENTION DEVICES:
 - ALL IRRIGATION SERVICES WITHIN RESIDENTIAL AREAS ARE REQUIRED TO HAVE BACKFLOW PREVENTION DEVICES.
 - ALL COMMERCIAL BACKFLOW PREVENTION DEVICES MUST BE APPROVED BY SAWS PRIOR TO INSTALLATION.
- FINAL CONNECTION TO THE EXISTING WATER MAIN SHALL NOT BE MADE UNTIL THE WATER MAIN HAS BEEN PRESSURE TESTED, CHLORINATED, AND SAWS HAS RELEASED THE MAIN FOR TIE-IN AND USE.

SEWER NOTES

- THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT NO SANITARY SEWER OVERFLOW (SSO) OCCURS AS A RESULT OF THEIR WORK. ALL CONTRACTOR PERSONNEL RESPONSIBLE FOR SSO PREVENTION AND CONTROL SHALL BE TRAINED ON PROPER RESPONSE. SHOULD AN SSO OCCUR, THE CONTRACTOR SHALL:
 - IDENTIFY THE SOURCE OF THE SSO AND NOTIFY SAWS EMERGENCY OPERATIONS CENTER (EOC) IMMEDIATELY AT (210) 233-2014. PROVIDE THE ADDRESS OF THE SPILL AND AN ESTIMATED VOLUME OR FLOW.
 - ATTEMPT TO ELIMINATE THE SOURCE OF THE SSO.
 - CONTAIN SEWAGE FROM THE SSO TO THE EXTENT OF PREVENTING A POSSIBLE CONTAMINATION OF WATERWAYS.
 - CLEAN UP SPILL SITE (RETURN CONTAINED SEWAGE TO THE COLLECTION SYSTEM IF POSSIBLE) AND PROPERLY DISPOSE OF CONTAMINATED SOIL/MATERIALS.
 - CLEAN THE AFFECTED SEWER MAINS AND REMOVE ANY DEBRIS.
 - MEET ALL POST-SSO REQUIREMENTS AS PER THE EPA CONSENT DECREE, INCLUDING LINE CLEANING AND TELEVISIONING THE AFFECTED SEWER MAINS (AT SAWS DIRECTION) WITHIN 24 HOURS.SHOULD THE CONTRACTOR FAIL TO ADDRESS AN SSO IMMEDIATELY AND TO SAWS SATISFACTION, THEY WILL BE RESPONSIBLE FOR ALL COSTS INCURRED BY SAWS, INCLUDING ANY FINES FROM EPA, TCEQ AND/OR ANY OTHER FEDERAL, STATE OR LOCAL AGENCIES.
- NO SEPARATE MEASUREMENT OR PAYMENT SHALL BE MADE FOR THIS WORK. ALL WORK SHALL BE DONE ACCORDING TO GUIDELINES SET BY THE TCEQ AND SAWS.
- IF BYPASS PUMPING IS REQUIRED, THE CONTRACTOR SHALL PERFORM SUCH WORK IN ACCORDANCE WITH SAWS STANDARD SPECIFICATION FOR WATER AND SANITARY SEWER CONSTRUCTION, ITEM NO. 864, "BYPASS PUMPING".
- PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING FORCE MAINS OF ANY SIZE MUST BE COORDINATED WITH THE SAWS CONSTRUCTION INSPECTION DIVISION AT (210) 233-2973 AT LEAST ONE WEEK IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO SAWS OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WORK ACCORDINGLY.
- SEWER PIPE WHERE WATER LINE CROSSES SHALL BE 160 PSI AND MEET THE REQUIREMENTS OF ASTM D2241, TAC 217.33 AND TCEQ 290.44(E)(4)(B). CONTRACTOR SHALL CENTER A 20' JOINT OF 160 PSI PRESSURE RATED PVC AT THE PROPOSED WATER CROSSING.
- ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ALLOWANCES AND ADJUSTMENTS FOR TOP OF MANHOLES TO MATCH THE FINISHED GRADE OF THE PROJECT'S IMPROVEMENTS. (NSP)
- SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER: ALL SPILLS, OVERFLOWS, OR DISCHARGES OF WASTEWATER, RECYCLED WATER, PETROLEUM PRODUCTS, OR CHEMICALS MUST BE REPORTED IMMEDIATELY TO THE SAWS INSPECTOR ASSIGNED TO THE COUNTER PERMIT OR GENERAL CONSTRUCTION PERMIT (GCP). THIS REQUIREMENT APPLIES TO EVERY SPILL, OVERFLOW, OR DISCHARGE REGARDLESS OF SIZE.
- MANHOLE AND ALL PIPE TESTING (INCLUDING THE TV INSPECTION) MUST BE PERFORMED AND PASSED PRIOR TO FINAL FIELD ACCEPTANCE BY SAWS CONSTRUCTION INSPECTION DIVISION, AS PER THE SAWS SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.
- ALL PVC PIPE OVER 14 FEET OF COVER SHALL BE EXTRA STRENGTH WITH MINIMUM PIPE STIFFNESS OF 115 PSI.



F.H.#4 EXISTING


BLOCK 12, LOT 2
VOLUME 10395, PAGE 0453
DEED AND PLAT RECORDS
BEXAR COUNTY, TEXAS

LOT 1

8" WWL PVC EXISTING
DJ-4609, SLOPE 0.4%

F.H.#2 EXISTING

VERIFY LOCATION AND DEPTH
DURING CONSTRUCTION




SITE LOCATION MAP

R=1228.06'
A=42.55'
C=42.55'
BRG=N 59°03'42" E
D=1°59'07"

LOT 3

S 32°15'13" E 231.80'
(S 32°08'47" E 231.56')



ELECTRICAL UNDERGROUND CABLE

6" WWL SDR26 SLOPE 1%

WW.MH. EXISTING

FOUND MAG NAIL BEARS
N 67°53'20" W 4.20'

N 23°47'07" W 89.82'
(N 23°40'41" W)

N 32°34'10" W 121.38'
(N 32°27'44" W)

8" WWL PVC EXISTING
DJ-4609, SLOPE 4.4%

24" WL EXISTING

BANDERA ROAD (S.H.16)

(VARIABLE WIDTH R.O.W.)

REFER SAWS SPECIFICATIONS ITEM NO: 3000 FOR HANDLING ASBESTOS CEMENT PIPE

ELECTRIC, TELEPHONE, GAS, ANCHOR, SERVICE, OVERHANG

R.D.

N 57°42'38" E
N 57°52'44" E
50.09' (50.10')

WESTCHASE STREET
(60' R.O.W.)



0 20 40
GRAPHIC SCALE 1"=20'-0"

8" WWL PVC EXISTING
DJ-4609, SLOPE 2.19%

12" AC
97-1097

F.H.#1 EXISTING

FIRE HYDRANT PROPOSED
1) INSTALL 1-8"x12" SADDLE
2) INSTALL 1-8" G.V.
3) INSTALL 8" WL, C900, 64.0 LF

WATER DOMESTIC SERVICE
1) 1-12"x1" SERVICE TAP
2) 1-1" WATER METER
3) 1" COPPER SERVICE WATER LINE
AS PER SAWS DD-824-01

WATER IRRIGATION SERVICE
1) 1-12"x1" SERVICE TAP
2) 1-1" WATER METER
3) 1" COPPER SERVICE WATER LINE
4) 1- 1" DCVA
AS PER SAWS DD-824-01

INSTALL 1-1" G.V.
INSTALL 1" SCH 40 WATER LINE

8" WWL PVC EXISTING
DJ-4609, SLOPE 2.19%

WW.MH. EXISTING

12" WL EXISTING

(1) INSTALL 6" SS LATERAL SDR26, LENGTH=4'-0"
AS PER SAWS DD-854-03
(2) INSTALL 6"CO
AS PER PER SAWS DD-854-02

Professional Structural Engineers, Inc. Consulting Civil and Structural Engineers

12710 RESEARCH BLVD., SUITE 200, AUSTIN, TX 78758 | TEL: 512.238.6420 | FAX: 512.238.6566



Project: BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Title: UTILITY SITE PLAN

30434

8

OF 25



2" Flanged Angle Valve (Ball-type only)

2" Strainer

8CH 80 Insulating Coupling

Prop. Line

Water Main

Concrete Base (Where Required)

2" Corporation Stop Up & Coupler

Normal Pipe Size x 2" Tapped Blue Tee

1 1/2" & 2" SERVICE TAPPED TEE


Note: For street tap to main, see Tapping Schedule


PROPERTY OF
ANTONIO WATER SYSTEM
SAN ANTONIO, TEXAS

COPPER
SERVICE INSTALLATION
TAPPING SCHEDULE


APPROVED
March 2008

DD-824-01





PLAN
SCALE: 1" = 3'




PROFILE
SCALE: 1" = 3'


GENERAL NOTES

1. THE LENGTH OF THE TYPE 1 CONSTRUCTION EXIT SHALL BE AS INDICATED ON THE PLANS, BUT NOT LESS THAN 50'.
2. THE COARSE AGGREGATE SHOULD BE OPEN GRADED WITH A SIZE OF 4" TO 8".
3. THE APPROACH TRANSITIONS SHOULD BE NO STEEPER THAN 6 : 1 AND CONSTRUCTED AS DIRECTED BY THE ENGINEER.
4. THE CONSTRUCTION EXIT FOUNDATION COURSE SHALL BE FLEXIBLE BASE, BITUMINOUS CONCRETE, PORTLAND CEMENT CONCRETE OR OTHER MATERIAL AS APPROVED BY THE ENGINEER.
5. THE CONSTRUCTION EXIT SHALL BE GRADED TO ALLOW DRAINAGE TO A SEDIMENT TRAPPING DEVICE.
6. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

CONSTRUCTION EXIT - TYPE 1




PLAN
SCALE: 1" = 5'




ELEVATION
SCALE: 1" = 5'

NOTE: STRADDLE GRAVEL FILTER BAGS WITH TYPE 1 BARRICADES MOUNTED WITH TYPE "A" FLASHING WARNING LIGHT. SEE BARRICADE CONSTRUCTION SIGN DETAILS. PLACE FLASHING LIGHTS AWAY FROM GUTTER, FLUSH WITH OUTSIDE EDGE OF BAG CONFIGURATION.

GRAVEL FILTER BAGS



PLAN
SCALE: 1" = 3'




PROFILE
SCALE: 1" = 3'

GENERAL NOTES

1. THE LENGTH OF THE TYPE 2 CONSTRUCTION EXIT SHALL BE AS INDICATED ON THE PLANS, BUT NOT LESS THAN 50'.
2. THE TREATED TIMBER PLANKS SHALL BE ATTACHED TO THE RAILROAD TIES WITH 1 / 2" x 6" MIN. LAG BOLTS. OTHER FASTENERS MAY BE USED AS APPROVED BY THE ENGINEER.
3. THE TREATED TIMBER PLANKS SHALL BE #2 GRADE MIN., AND SHOULD BE FREE FROM LARGE AND LOOSE KNOTS.
4. THE APPROACH TRANSITIONS SHOULD BE NO STEEPER THAN 6 : 1 AND CONSTRUCTED AS DIRECTED BY THE ENGINEER.
5. THE CONSTRUCTION EXIT FOUNDATION COURSE SHALL BE FLEXIBLE BASE, BITUMINOUS CONCRETE, PORTLAND CEMENT CONCRETE OR OTHER MATERIAL AS APPROVED BY THE ENGINEER.
6. THE CONSTRUCTION EXIT SHOULD BE GRADED TO ALLOW DRAINAGE TO A SEDIMENT TRAPPING DEVICE.
7. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.


CONSTRUCTION EXIT - TYPE 2




PLAN
SCALE: 1" = 5'

NOTE: GRAVEL FILTERS CAN BE USED ON PAVEMENT OR BARE GROUND.

CURB INLET GRAVEL FILTER



PLAN
SCALE: 1" = 10'




SECTION A-A
SCALE: 1" = 1'


GENERAL NOTES

1. THE LENGTH OF THE TYPE 3 CONSTRUCTION EXIT SHALL BE AS INDICATED ON THE PLANS, OR AS DIRECTED BY THE ENGINEER.
2. THE TYPE 3 CONSTRUCTION EXIT MAY BE CONSTRUCTED FROM OPEN GRADED CRUSHED STONE WITH A SIZE OF 2 TO 4 INCHES SPREAD A MINIMUM OF 4 INCHES THICK TO THE LIMITS SHOWN ON THE PLANS.
3. THE TREATED TIMBER PLANKS SHALL BE #2 GRADE MIN., AND SHOULD BE FREE FROM LARGE AND LOOSE KNOTS.
4. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

CONSTRUCTION EXIT - TYPE 3



SECTION C-C
SCALE: 1" = 1'



ISOMETRIC VIEW
SCALE: 1" = 1'

SEDIMENT CONTROL FENCE USAGE GUIDELINES

A SEDIMENT CONTROL FENCE MAY BE CONSTRUCTED NEAR THE DOWNSTREAM PERIMETER OF A DISTURBED AREA ALONG A CONTOUR TO INTERCEPT SEDIMENT FROM OVERLAND RUN-OFF. A 2 YEAR STORM FREQUENCY MAY BE USED TO CALCULATE THE FLOW RATE TO BE FILTERED.

SEDIMENT CONTROL FENCE SHOULD BE SIZED TO FILTER A MAXIMUM FLOW THRU RATE OF 100 GPM / FT SQUARED. SEDIMENT CONTROL FENCE IS NOT RECOMMENDED TO CONTROL EROSION FROM A DRAINAGE AREA LARGER THAN 2 ACRES.

GENERAL NOTES

1. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.

TEMPORARY SEDIMENT CONTROL FENCE

JANUARY 2005

STANDARD PLANS
CITY OF SAN ANTONIO, TEXAS
DEPARTMENT OF PUBLIC WORKS

TEMPORARY EROSION, SEDIMENT &
WATER POLLUTION CONTROL
MEASURES STANDARDS 1

DRAWN BY:	DATE:	REVISIONS:	SCALE:
V. VASQUEZ			SEE ABOVE
CHECKED BY:	DATE:		
NAT HARDY, P.E.			
		SHEET:	OF


Project: BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

30434


Table: GENERAL DETAILS

11 OF 25


PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78758 TEL: 512-238-8421 FAX: 512-238-8086




PROFILE VIEW
SCALE : 1" = 1'



PLAN VIEW
SCALE : 1" = 1'



SECTION B-B
SCALE : 1" = 1'



BALED HAY USAGE GUIDELINES

A BAILED HAY INSTALLATION MAY BE CONSTRUCTED NEAR THE DOWNSTREAM PERIMETER OF A DISTURBED AREA ALONG A CONTOUR TO INTERCEPT SEDIMENT FROM OVERLAND RUNOFF. A TWO YEAR STORM FREQUENCY MAY BE USED TO CALCULATE THE FLOW RATE TO BE FILTERED. THE INSTALLATION SHOULD BE SIZED TO FILTER A MAXIMUM FLOW THRU RATE OF 5 GPM / FT SQUARED OF CROSS SECTIONAL AREA. BAILED HAY MAY BE USED AT THE FOLLOWING LOCATIONS:

1. WHERE THE RUNOFF APPROACHING THE BAILED HAY FLOWS OVER DISTURBED SOIL FOR LESS THAN 100'. IF THE SLOPE OF THE DISTURBED SOIL EXCEEDS 10 %, THE LENGTH OF SLOPE UPSTREAM OF THE BAILED HAY SHOULD BE LESS THAN 50'.
2. WHERE THE INSTALLATION WILL BE REQUIRED FOR LESS THAN 3 MONTHS.
3. WHERE THE CONTRIBUTING DRAINAGE AREA IS LESS THAN 1 / 2 ACRE.

FOR BAILED HAY INSTALLATIONS IN SMALL DITCHES, THE FOLLOWING ADDITIONAL CONSIDERATIONS APPLY:


1. THE DITCH SIDESLOPES SHOULD BE GRADED AS FLAT AS POSSIBLE TO MAXIMIZE THE DRAINAGE FLOW RATE THRU THE HAY.
2. THE DITCH SHOULD BE GRADED LARGE ENOUGH TO CONTAIN THE OVERLAPPING DRAINAGE WHEN SEDIMENT HAS FILLED TO THE TOP OF THE BAILED HAY.

BALES SHOULD BE REPLACED USUALLY EVERY 2 MONTHS OR MORE OFTEN DURING WET WEATHER WHEN LOSS OF STRUCTURAL INTEGRITY IS ACCELERATED.


GENERAL NOTES

1. HAY BALES SHALL BE A MINIMUM OF 30" IN LENGTH AND WEIGH A MINIMUM OF 50 LBS.
2. HAY BALES SHALL BE BOUND BY EITHER WIRE OR NYLON OR POLYPROPYLENE STRING. THE BALES SHALL BE COMPOSED ENTIRELY OF VEGETABLE MATTER.
3. HAY BALES SHALL BE EMBEDDED IN THE SOIL A MINIMUM OF 4" AND, WHERE POSSIBLE, ONE-HALF THE HEIGHT OF THE BALE.
4. HAY BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BALES. THE BALES SHALL BE PLACED WITH BINDINGS PARALLEL TO THE GROUND.
5. HAY BALES SHALL BE SECURELY ANCHORED IN PLACE WITH 3 / 8" DIA. REBAR OR 2" x 2" WOOD STAKES DRIVEN THROUGH THE BALES. THE FIRST STAKE SHALL BE ANGLED TOWARDS THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER.
6. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.


BALED HAY FOR EROSION CONTROL




TYPE 1 FILTER DAM AT
TOE OF SLOPE
SCALE : 1" = 5'



TYPE 1 & 2 FILTER DAM AT
SEDIMENT TRAP
SCALE : 1" = 5'




TYPE 1, 2 & 3 FILTER DAM
AT CHANNEL SECTIONS
SCALE : 1" = 3'




PLAN VIEW
SCALE : 1" = 5'


TYPE 4 FILTER DAM AT DITCHES
& SMALLER CHANNELS PLAN VIEW




PROFILE OF TYPE 1 & 2 FILTER
DAM AT SEDIMENT TRAP
SCALE : 1" = 3'



SECTION D-D
SCALE : 1" = 3'



"V" SHAPE
PLAN VIEW
NOT TO SCALE



SECTION E-E
SCALE : 1" = 5'

ROCK FILTER DAMS

ROCK FILTER DAM USAGE GUIDELINES

ROCK FILTER DAMS SHOULD BE CONSTRUCTED DOWNSTREAM FROM DISTURBED AREAS TO INTERCEPT SEDIMENT FROM OVERLOAD RUNOFF AND / OR CONCENTRATED FLOW. THE DAMS SHOULD BE SIZED TO FILTER A MAXIMUM FLOW THRU RATE OF 60 GPM / FT SQUARED OF CROSS SECTIONAL AREA. A 2 YEAR STORM FREQUENCY MAY BE USED TO CALCULATE THE FLOW RATE.

TYPE 1 (18" HIGH WITH NO WIRE MESH) :

TYPE 1 MAY BE USED AT THE TOE OF SLOPES, AROUND INLETS, IN SMALL DITCHES AND AT DIKE OR SWALE OUTLETS. THIS TYPE OF DAM IS RECOMMENDED TO CONTROL EROSION FROM A DRAINAGE AREA OF 5 ACRES OR LESS. TYPE 1 MAY NOT BE USED IN CONCENTRATED HIGH VELOCITY FLOWS (APPROXIMATELY 8 FT. / SEC. OR MORE) IN WHICH AGGREGATE WASH OUT MAY OCCUR. SANDBAGS MAY BE USED AT THE EMBEDDED FOUNDATION (4" DEEP MIN.) FOR BETTER FILTERING EFFICIENCY OF LOW FLOWS IF CALLED FOR ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

TYPE 2 (18" HIGH WITH WIRE MESH) :

TYPE 2 MAY BE USED IN DITCHES AND AT DIKE OR SWALE OUTLETS.

TYPE 3 (36" HIGH WITH WIRE MESH) :


TYPE 3 MAY BE USED IN STREAM FLOW AND SHOULD BE SECURED TO THE STREAM BED.

TYPE 4 (SACK GABIONS) :

TYPE 4 MAY BE USED IN DITCHES AND SMALLER CHANNELS TO FORM AN EROSION CONTROL DAM.

GENERAL NOTES

1. IF SHOWN ON THE PLANS OR DIRECTED BY THE ENGINEER, FILTER DAMS SHOULD BE PLACED NEAR THE TOE OF SLOPES WHERE EROSION IS ANTICIPATED, UPSTREAM AND / OR DOWNSTREAM AT DRAINAGE STRUCTURES, AND IN ROADWAY DITCHES AND CHANNELS TO COLLECT SEDIMENT.
2. MATERIALS (AGGREGATE, WIRE MESH, SANDBAGS, ETC.) SHALL BE AS INDICATED BY THE SPECIFICATION FOR ROCK FILTER DAMS FOR EROSION AND SEDIMENTATION CONTROL.
3. THE ROCK FILTER DAM DIMENSIONS SHALL BE AS INDICATED ON THE STORM WATER POLLUTION PREVENTION PLANS.
4. SIDE SLOPES SHOULD BE 2 : 1 OR FLATTER. DAMS WITHIN THE SAFETY ZONE SHALL HAVE SIDE SLOPES OF 6 : 1 OR FLATTER.
5. MAINTAIN A MINIMUM OF 1' BETWEEN TOP OF ROCK FILTER DAM WEIR AND TOP OF EMBANKMENT FOR FILTER DAMS AT SEDIMENT TRAPS.
6. FILTER DAMS SHOULD BE EMBEDDED A MINIMUM OF 4" INTO THE EXISTING GROUND.
7. THE SEDIMENT TRAP FOR PONDING OF SEDIMENT LADEN RUNOFF SHALL BE OF THE DIMENSIONS SHOWN ON THE PLANS.
8. ROCK FILTER DAM TYPES 2 & 3 SHALL BE SECURED WITH 20 GAUGE GALVANIZED WOVEN WIRE MESH WITH 1" DIAMETER HEXAGONAL OPENINGS. THE AGGREGATE SHALL BE PLACED ON THE MESH TO THE HEIGHT AND SLOPES SPECIFIED. THE MESH SHALL BE FOLDED AT THE UPSTREAM SIDE OVER THE AGGREGATE AND TIGHTLY SECURED TO ITSELF ON THE DOWNSTREAM SIDE USING WIRE TIES OR HOG RINGS. IN STREAM USE, THE MESH SHOULD BE SECURED OR STAKED TO THE STREAM BED PRIOR TO AGGREGATE PLACEMENT.
9. SACK GABIONS SHOULD BE STAKED DOWN WITH 3 / 4" DIA. REBAR STAKES.
10. FLOW OUTLET SHOULD BE ONTO A STABILIZED AREA (VEGETATION, ROCK, ETC.).
11. THE GUIDELINES SHOWN HEREON ARE SUGGESTIONS ONLY AND MAY BE MODIFIED BY THE ENGINEER.



TYPE 4 SACK GABION DETAIL
SCALE : 1" = 3'



SECTION F-F
SCALE : 1" = 3'

JANUARY 2005

STANDARD PLANS
CITY OF SAN ANTONIO, TEXAS
DEPARTMENT OF PUBLIC WORKS

TEMPORARY EROSION, SEDIMENT &
WATER POLLUTION CONTROL
MEASURES STANDARDS 2

DRAWN BY: V. VASQUEZ	DATE	REVISIONS	SCALE: SEE ABOVE
CHECKED BY: NAT HARDY, P.E.			DATE:
			SHEET: OF




THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHRIR BAIG, P.E., #62577 ON 04/20/2018 FIRM REGISTRATION F-4951

PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78759 | TEL. 912.238.6421 | FAX 912.238.6095


PROJECT:
BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS
Title:
GENERAL DETAILS

30434
SHEET
12
OF 25




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK ABUTTING CURB
ITEM 503.1



TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS ABUTTING CURB
ITEM 503.1



TYPICAL COMMERCIAL DRIVEWAY SECTION


WITH SIDEWALK ABUTTING CURB
ITEM 503.2

CONCRETE DRIVEWAY NOTES

- DRIVEWAY PENETRATION REFERS TO A PORTION OF THE DRIVEWAY THAT MAY BE NECESSARY TO RECONSTRUCT WITHIN PRIVATE PROPERTY TO COMPLY WITH A MAXIMUM DRIVEWAY SLOPE. THIS PORTION OF THE DRIVEWAY SHALL BE PAID FOR UNDER THE FOLLOWING ITEMS AS MAY APPLY:
A) CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.1 OR 503.2.
B) ASPHALTIC CONCRETE DRIVEWAY PAID FOR UNDER ITEM NO. 503.4 AND SHALL INCLUDE A MINIMUM OF 1" ASPHALT TYPE 'D' & 6" FLEXIBLE BASE.
C) GRAVEL DRIVEWAY PAID FOR UNDER ITEM NO. 503.5 AND SHALL INCLUDE A MINIMUM OF 6" FLEXIBLE BASE.
- 7" MINIMUM HEIGHT WILL NOT NECESSARILY OCCUR AT THE PROPERTY LINE. IT MAY OCCUR WITHIN THE RIGHT OF WAY OR WITHIN THE DRIVEWAY PENETRATION ON PRIVATE PROPERTY.
- THE PROPOSED DRIVEWAY SHOULD MATCH THE EXISTING WIDTH AT THE PROPERTY LINE BUT UNLESS AUTHORIZED BY THE CITY TRAFFIC ENGINEER, THE WIDTH SHALL BE WITHIN THE FOLLOWING VALUES:


TYPE	MINIMUM	MAXIMUM
RESIDENTIAL	10'	20'
COMMERCIAL - ONE WAY	12'	20'
COMMERCIAL - TWO WAY	24'	30'

- FOR LOCAL TYPE "A" STREETS, SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 2' FROM THE BACK OF CURB.
- FOR OTHER THAN LOCAL TYPE "A" STREETS, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 4' AND SEPARATED A MINIMUM OF 2' FROM THE BACK OF CURB OR, AS AN OPTION, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
- DUMMY JOINTS PARALLEL TO THE CURB SHALL BE PLACED WHERE THE SIDEWALK MEETS THE DRIVEWAY. DUMMY JOINTS PERPENDICULAR TO THE CURB, AND WITHIN THE BOUNDARIES OF THE PARALLEL DUMMY JOINTS, SHALL BE PLACED AT INTERVALS EQUAL TO THE WIDTH OF THE SIDEWALK.
- A MINIMUM OF TWO ROUND AND SMOOTH DOWEL BARS 3/8" IN DIAMETER AND 18" IN LENGTH SHALL BE SPACED 18" APART AT EACH EXPANSION JOINT.
- SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE. WHERE SIDEWALKS CROSS DRIVEWAYS, SIDEWALK CROSS SLOPE SHALL NOT EXCEED 2%.
- SIDEWALK RAMP SURFACE SHALL BE BRUSH FINISHED.




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WITH SIDEWALK SEPARATED FROM CURB
ITEM 503.1




TYPICAL RESIDENTIAL DRIVEWAY SECTION

WHERE PROPERTY IS LOWER THAN STREET & SIDEWALK IS SEPARATED FROM CURB
ITEM 503.1



TYPICAL COMMERCIAL DRIVEWAY SECTION


WITH SIDEWALK SEPARATED FROM CURB
ITEM 503.2



- NOTE:
- COST OF REINFORCEMENT TO BE INCLUDED IN UNIT COST OF ITEM 307.1.
 - CONCRETE RETAINING WALL COMBINATION TYPE SHALL BE USED FOR CONCRETE DRIVEWAYS.


DRIVEWAY - CONCRETE RETAINING WALL

ON COMPACTED SUBGRADE
ITEM 307.1




CURB PROFILE AT DRIVEWAY

WITH SIDEWALK ABUTTING CURB




TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK ABUTTING CURB



CURB PROFILE AT DRIVEWAY

WITH SIDEWALK SEPARATED FROM CURB



TYPICAL DRIVEWAY PLAN VIEW

WITH SIDEWALK SEPARATED FROM CURB

MAY 2009

CITY OF SAN ANTONIO

CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

CONCRETE DRIVEWAY STANDARDS

% SUBMITTAL PROJECT NO.: DATE:
DRWN. BY: V. VASQUEZ DSGN. BY: CHKD. BY: R.S. HOSSEINI, P.E. SHEET NO.: OF

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHER BAG, P.E., #82577 ON 04/20/2018 FIRM REGISTRATION F-4951







PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78759 (TEL: 512.238.6420) (FAX: 512.258.8095)


















Project: BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

Title: GENERAL DETAILS

30434

13 OF 25





MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

MISCELLANEOUS CONSTRUCTION STANDARDS I

Project: 30434
Project No.:
Date:
Drawn By: V. VASQUEZ
Design By:
Checked By: R.S. HOSSEINI, P.E.
Sheet No.: OF

Project: 30434
Project No.:
Date:
Drawn By: V. VASQUEZ
Design By:
Checked By: R.S. HOSSEINI, P.E.
Sheet No.: OF

GENERAL DETAILS

15 OF 25

PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78759 TEL: 512-338-6402 FAX: 512-338-6095

BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS



MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

MISCELLANEOUS CONSTRUCTION STANDARDS I

Project: 30434
Project No.:
Date:
Drawn By: V. VASQUEZ
Design By:
Checked By: R.S. HOSSEINI, P.E.
Sheet No.: OF

GENERAL DETAILS


15 OF 25




TYPICAL SIDEWALK RAMP - TYPE II
USED AT TEE INTERSECTIONS WHERE SIDEWALK ABUTS CURB
SCALE: 1"=10'

GENERAL NOTES


1. WHEN POSSIBLE SIDEWALKS SHOULD BE PLACED NEXT TO THE PROPERTY LINE, ALLOWING A MINIMUM OF 1 FOOT BUFFER. DEVIATION OF THE PATHWAY FROM A STRAIGHT LINE IS ENCOURAGED TO AVOID TREES OR OTHER OBSTRUCTIONS.
2. FOR LOCAL TYPE "A" STREETS, SIDEWALKS SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4' AND IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL BE LOCATED A MINIMUM OF 2' FROM THE BACK OF CURB.
3. FOR OTHER THAN LOCAL TYPE "A" STREETS, SIDEWALKS SHALL HAVE A MINIMUM UNOBSTRUCTED WIDTH OF 4' AND SEPARATED A MINIMUM OF 2' FROM THE BACK OF CURB. IF SEPARATED FROM THE CURB, THE SIDEWALK SHALL HAVE A MINIMUM WIDTH OF 6' WHEN LOCATED AT THE BACK OF CURB.
4. SIDEWALK RAMP LENGTHS PRESENTED IN TABLE 1 ARE GUIDELINES ONLY. SIDEWALK RAMP LENGTHS SHALL BE OF SUFFICIENT LENGTH TO MAINTAIN 8.33% (1:12) MAXIMUM SLOPE.
5. ALL CURB-RAMPS OR LANDINGS ABUTTING THE CROSSWALK SHALL HAVE A DETECTABLE WARNING 24 INCHES DEEP (IN THE DIRECTION OF PEDESTRIAN TRAVEL) AND EXTENDING THE FULL WIDTH OF THE CURB RAMP OR LANDING. THE DETECTABLE WARNING SHALL CONSIST OF RAISED TRUNCATED DOMES, ALIGNED IN A GRID PATTERN WITH A DIAMETER OF A NOMINAL 0.9 INCHES (23 MM), A HEIGHT OF NOMINAL 0.2 INCHES (5 MM) AND A CENTER-TO-CENTER SPACING OF NOMINAL 2.35 INCHES (60 MM). THE DETECTABLE WARNING SURFACE SHALL BE A CAST-IN-PLACE TILE CONFORMING TO THE CITY OF SAN ANTONIO STANDARD SPECIFICATIONS OR PAVERS CONFORMING TO TxDOT STANDARD PED-05, PEDESTRIAN FACILITIES.
6. DETECTABLE WARNINGS SHALL CONTRAST VISUALLY WITH ADJOINING SURFACES, EITHER LIGHT-ON-DARK, OR DARK-ON-LIGHT. THE MATERIAL USED TO PROVIDE CONTRAST SHALL BE AN INTEGRAL PART OF THE WALKING SURFACE.
7. SIDEWALK RAMP TYPE V SHALL BE USED ONLY WHERE THERE IS SIGNIFICANT RESTRICTION WITHIN THE PARKWAY TO CONSTRUCT TYPE I OR TYPE III RAMPS.
8. CONSTRUCTION OF ALL WHEELCHAIR RAMPS TO BE INCLUDED UNDER ITEMS "500 - CONCRETE CURB, GUTTER, AND CONCRETE CURB AND GUTTER" AND/OR "502 - CONCRETE SIDEWALKS". RAMP SURFACE SHALL BE BRUSH FINISHED.
9. THESE DETAILS ARE FOR REFERENCE ONLY. ACTUAL LOCATIONS OF WHEELCHAIR RAMPS TO BE SHOWN ON CONSTRUCTION PLANS. CITY CONSTRUCTION INSPECTOR CAN ADJUST LOCATIONS FOR SAFETY OR UTILITY CLEARANCE.
10. SIDEWALKS LESS THAN 5 FEET IN WIDTH SHALL BE PROVIDED WITH A PASSING SPACE AT A MAXIMUM SPACING OF 200 FEET.
11. WHEELCHAIR RAMP SHALL BE CONSTRUCTED WITH 4" CLASS "A" CONCRETE AND 2" MINIMUM GRAVEL, CRUSHED ROCK OR FLEXIBLE BASE MATERIAL.
12. REINFORCING STEEL SHALL BE #3 BARS @ 18" O.C.E.W. OR 6" x 6" - W2.9 x W2.9 WIRE MESH.
13. SIDEWALK GRADES SHALL NOT EXCEED THE GRADE ESTABLISHED FOR THE ADJACENT ROADWAY. ANY SIDEWALK CONSTRUCTION THAT DEVIATES FROM THE NATURAL GRADE OF THE ROADWAY TO CREATE A GRADE STEEPER THAN THE EXISTING ROADWAY WILL REQUIRE RAMPS, HANDRAILS AND RESTING PLATFORMS TO BE CONSTRUCTED IN ACCORDANCE WITH ADA AND TAS STANDARDS.
14. SIDEWALK CROSS GRADE SHALL HAVE A MAXIMUM SLOPE OF 2%. LANDINGS SHALL HAVE A MAXIMUM SLOPE OF 2% IN ANY DIRECTION.
15. THE CHANGE OF GRADE BETWEEN ADJACENT SURFACES SHALL BE LESS THAN 11%. THE CHANGE OF GRADE SHALL BE DEFINED AS THE ALGEBRAIC DIFFERENCE OF THE ADJACENT SURFACE SLOPES. IN THE CASE OF A STREET ACCESS RAMP DESIGNED AT THE 8.33% MAXIMUM SLOPE, THE ADJACENT PAVEMENT CROSS SLOPE SHALL BE LESS THAN 2.67% (I.E. 8.33-(2.67)=11). IN ADDITION, THE ADJACENT PAVEMENT CROSS SLOPE SHALL BE LESS THAN OR EQUAL TO 5%.
16. IF THE CHANGE OF GRADE BETWEEN ADJACENT SURFACES IS GREATER THAN OR EQUAL TO 11%, A LEVELING STRIP, 2 FEET IN LENGTH, SHALL BE PROVIDED TO TRANSITION THE ADJACENT SURFACES.
17. ADA COMPLIANCE IN ALTERATIONS INCLUDE ONLY THAT WORK WITHIN THE LIMITS, BOUNDARIES OR SCOPE OF A PLANNED PROJECT.





TYPICAL SIDEWALK RAMP - TYPE III
SIDEWALK SEPARATED FROM CURB
SCALE: 1"=10'




TYPICAL SIDEWALK RAMP - TYPE IV
USED AT TEE INTERSECTIONS WHERE SIDEWALK IS SEPARATED FROM CURB
SCALE: 1"=10'




DETECTABLE WARNING SURFACE
SCALE: 1"=4'




TYPICAL SIDEWALK RAMP - TYPE V
SIDEWALK ABUTS CURB
SCALE: 1"=10'




SECTION C-C
CURB PROFILE WHERE SIDEWALK ABUTS CURB
SCALE: 1"=4'




SECTION D-D
CURB PROFILE WHERE SIDEWALK IS SEPARATED FROM CURB
SCALE: 1"=4'




SIDEWALK PASSING SPACE
SCALE: 1"=10'




SECTION A-A
SCALE: 1"=4'



SECTION B-B
SCALE: 1"=4'



SECTION C-C
CURB PROFILE WHERE SIDEWALK ABUTS CURB
SCALE: 1"=4'



SECTION D-D
CURB PROFILE WHERE SIDEWALK IS SEPARATED FROM CURB
SCALE: 1"=4'

TABLE 1 (SEE NOTE 4)		
GUTTER SLOPE	SIDEWALK RAMP LENGTH (1:12)	
	LOW SIDE	HIGH SIDE
1%	5'-6"	7'-2"
2%	5'-0"	8'-4"
3%	4'-6"	10'-0"
4%	4'-2"	12'-6"
5%	3'-10"	16'-8"

MAY 2009
CITY OF SAN ANTONIO
CAPITAL IMPROVEMENTS MANAGEMENT SERVICES DEPARTMENT

WHEELCHAIR RAMP STANDARDS

PROJECT: 30434
DATE: 05/01/09
DRAWN BY: V. VASQUEZ
DSGN. BY: V. VASQUEZ
CHKD. BY: R.S. HOSSEINI, P.E.
SHEET NO.: 16 OF 25


PROFESSIONAL STRUCTURAL ENGINEERS, INC.
CONSULTING CIVIL AND STRUCTURAL ENGINEERS
12710 RESEARCH BLVD., SUITE 300, AUSTIN, TX 78759 | TEL: 412.238.6422 | FAX: 412.238.6093

BANDERA RETAIL CENTER
7706 BANDERA ROAD, SAN ANTONIO, TEXAS

GENERAL DETAILS

THE SEAL APPEARING ON THIS DOCUMENT WAS AUTHORIZED BY MIRZA TAHRIR BAIG, P.E. #82577 ON 04/20/2019 FIRM REGISTRATION F-4951

16 OF 25




HYDRAULIC LOSS CHART	
MOST CRITICAL ZONE - ZONE 6R (TURF ROTOR)	15.3 GPM
STATIC WATER PRESSURE AVAILABLE**	100 PSI
SPRINKLER HEAD PRESSURE REQUIREMENT	45 PSI
IRRIGATION PIPE LOSS	0.98 PSI
1" REMOTE CONTROL VALVE LOSS	2.9 PSI
1 1/4" MAINLINE LOSS	2.5 PSI
1" MASTER VALVE LOSS	2.2 PSI
1" BACKFLOW PREVENTER LOSS	12.0 PSI
1" WATER METER LOSS	1.4 PSI
1" TYPE K COPPER SERVICE LINE LOSS	5.7 PSI
ELEVATION GAIN	-3.9 PSI
TOTAL SYSTEM PRESSURE LOSS	23.8 PSI
DESIGN PRESSURE (HEAD PRESSURE + TOTAL LOSS)	68.8 PSI

- GENERAL NOTES:
- COORDINATE ALL IRRIGATION WORK WITH PLANTING OPERATIONS.
 - REFER TO CIVIL PLANS FOR GRADING INFORMATION & FINAL GRADES.
 - IRRIGATION EQUIPMENT SHALL NOT BE INSTALLED IN BANDERA ROAD (TXDOT) R.O.W.

IRRIGATION INSPECTION
REQUIRED
CALL: 207-1111

I, Iris Puh (TX Licensed Irrigator #12060), do certify that the irrigation plans conform to the irrigation design & equipment standards set out in subsections 35-510 (j) & 35-511 (c) (6) of the City of San Antonio Unified Development Code.

IRRIGATION INSTALLATION SHALL FOLLOW ALL STATE OF TEXAS REGULATIONS INCLUDING: THE TEXAS OCCUPATIONS CODE CH 1903; TEXAS WATER CODE CH 37; TEXAS ADMINISTRATIVE CODE TITLE 30 CHAPTER 344 - LANDSCAPE IRRIGATION; TEXAS ADMINISTRATIVE CODE TITLE 30 CHAPTER 30 - OCCUPATIONAL LICENSES & REGISTRATIONS; CONTACT THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ), PO BOX 13087, AUSTIN, TX 78711 (WWW.TCEQ.TEXAS.GOV). IN ADDITION, FOLLOW ALL LOCAL IRRIGATION REQUIREMENTS IF MORE STRINGENT THAN STATE REGULATIONS.



(A) IRRIGATION PLAN
SCALE: 1" = 10'-0"



© 2018 PLACE MATRIX DESIGN OFFICE, LLC
ALL RIGHTS RESERVED. DOCUMENT MAY NOT BE REPRODUCED, COPIED, EDITED, OR PUBLISHED IN ANY FORMAT WITHOUT PRIOR WRITTEN PERMISSION OF PLACE MATRIX DESIGN OFFICE, LLC.



PROJECT NAME

BANDERA RETAIL CENTER
7706 BANDERA ROAD
SAN ANTONIO, TX 78238

PROJECT INFO.
PROJECT NUMBER: 201803
DRAWN BY: ISP
CHECKED BY: ISP
ISSUE DATE
04-16-2018

REVISIONS	
NUM	DESCRIPTION
1	CITY REVIEW COMMENTS

SHEET TITLE

IRRIGATION PLAN

SHEET NUMBER




IRRIGATION NOTES:

1. THESE NOTES SHALL BE USED IN ASSOCIATION WITH SPECIFICATION SECTION 32 84 00 ON IRRIGATION & THE DRAWING DETAILS.
2. PERFORM ALL WORK IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES, AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK AND PROVIDE FOR ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE, SAN ANTONIO WATER SYSTEM, AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION, AND INSTALLATION OF MATERIALS.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF ALL UNDERGROUND UTILITY LINES (TELEPHONE, GAS, WATER, SEWER, ELECTRICAL, PIPELINES, COMMUNICATION, CABLE, ETC.) AND ANY EASEMENTS PRIOR TO START OF ANY IRRIGATION WORK. CONTACT TEXAS 811 AT LEAST 48 HOURS PRIOR TO START OF ALL WORK.
4. CONTRACTOR SHALL REFER ALSO TO THE CIVIL / MEP PLANS FOR ALL PROPOSED SITE UTILITY & SITE GRADING WORK INFORMATION.
5. CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS SHOWN ON THE PLANS. IF A SITE CONFLICT IS PRESENT, THEN THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING ANY SITE IRRIGATION WORK.
6. ALL SITE GRADING & HARD SURFACE PAVING ADJACENT TO PLANTING AREAS, INCLUDING CONCRETE WALKS & ROAD WORK, MUST BE COMPLETED PRIOR TO START OF ANY IRRIGATION WORK. CONTRACTOR WILL BE RESPONSIBLE FOR ADJUSTING ELEVATIONS OF IRRIGATION EQUIPMENT IF INSTALLED AT IMPROPER ELEVATIONS.
7. CONTRACTOR SHALL COORDINATE ALL IRRIGATION INSTALLATION WORK WITH OTHER TRADES TO PREVENT ANY WORK CONFLICTS.
8. CONTRACTOR SHALL FOLLOW ALL TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) REGULATIONS FOR IRRIGATION WORK. A LICENSED IRRIGATOR OR LICENSED IRRIGATION TECHNICIAN MUST BE PRESENT AT THE PROJECT SITE TO OVERSEE ALL IRRIGATION INSTALLATION WORK.
9. VERIFY ON SITE STATIC WATER PRESSURE. IF PRESSURE IS LESS THAN THE DESIGN PRESSURE, NOTIFY THE LANDSCAPE ARCHITECT BEFORE CONTINUING WORK. IF PRESSURE IS SIGNIFICANTLY HIGHER THAN THE DESIGN PRESSURE, THEN INSTALL A PRESSURE REDUCING VALVE SPECIFIED FOR THE SYSTEM.
10. IRRIGATION WORK
- A. ALL IRRIGATION EQUIPMENT FURNISHED SHALL BE NEW & PER THE SPECIFICATION REQUIREMENTS OF THIS PROJECT. EQUIPMENT SUBSTITUTIONS ARE NOT ALLOWED UNLESS APPROVED IN WRITING.
- B. ALL IRRIGATION EQUIPMENT SHALL BE INSTALLED WITHIN THE PROPERTY LINES, UNLESS HEADS ARE SHOWN IN THE R.O.W.
- C. IRRIGATION SYSTEM LAYOUT IS DIAGRAMMATIC ONLY. MINOR ADJUSTMENTS TO ACCOMMODATE ACTUAL SITE CONDITIONS MAY BE NECESSARY. ADJUST HEAD & PIPING LOCATIONS TO FOLLOW THE INTENT OF THE DESIGN.
- D. MAJOR DEVIATIONS FROM THE DESIGN LAYOUT IS NOT PERMITTED. IF INSTALLATION AREA DIMENSIONS DEVIATE FROM LAYOUT SHOWN ON THE DRAWINGS & THE IRRIGATION DESIGN NEEDS TO BE SIGNIFICANTLY ALTERED, THEN CONTACT THE LANDSCAPE ARCHITECT FOR DIRECTION. IF CONTRACTOR PROCEEDS WITHOUT GIVING NOTIFICATION, THEN THE CONTRACTOR SHALL ASSUME FULL RESPONSIBILITY FOR ANY REVISIONS MADE TO THE DESIGN.
- E. HEAD SPACING SHALL NOT EXCEED THE MANUFACTURER'S PUBLISHED RADIUS. ALL IRRIGATION PVC PIPE SHALL BE PROGRESSIVE SIZED SO THAT VELOCITY THROUGH PIPE DOES NOT EXCEED 5 FT/SEC. IF MODIFICATIONS TO THE PIPING DESIGN ARE NEEDED, THEN THE FOLLOWING GUIDELINES SHALL BE USED FOR CLASS 200 PIPE:
- | | |
|-------------------------------------|------------------------------|
| 1/2" PIPE (CLASS 315) - UP TO 5 GPM | 1 1/4" PIPE - 16.1 TO 26 GPM |
| 3/4" PIPE - 5.1 TO 10 GPM | 1 1/2" PIPE - 26.1 TO 35 GPM |
| 1" PIPE - 10.1 TO 16 GPM | 2" PIPE - 35.1 TO 55 GPM |
- F. ALL IRRIGATION SLEEVES SHALL BE SCHEDULE 40 PVC PIPE AT 2 TIMES THE DIAMETER OF THE IRRIGATION PIPE TO BE SLEEVED OR A MIN. OF 4" DIAMETER PIPE, WHICHEVER IS GREATER. EXTEND SLEEVES 24" BEYOND PAVEMENT OR WALL WIDTH ON BOTH SIDES.
- G. ALL SPRINKLER HEADS SHALL BE INSTALLED A MIN. OF 6" AWAY FROM ALL PAVEMENT, CURBS, OR STRUCTURES. INSTALL SPRINKLER HEADS A MIN. OF 12" AWAY FROM A BUILDING EDGE.
- H. IRRIGATION TRENCH DEPTHS: 12" MIN. FOR LATERAL LINES, 18" MIN. FOR MAIN LINES, 24" MIN. FOR PIPING UNDER TRAFFIC LOADS, & 4" OR 6" FOR DRIP LINES.
- I. ALL THREADED PIPE & FITTINGS SHALL BE SCHEDULE 80 PVC.
- J. FOR ALL PVC PIPE & FITTINGS INSTALLED, USE PURPLE PRIMER PRIOR TO SOLVENT WELDING.
- K. INSTALL DRAIN GRAVEL IN ALL VALVE BOXES & ELSEWHERE AS CALLED OUT ON THE DRAWINGS & SPECIFICATIONS.
- L. QUICK COUPLING VALVES SHALL BE INSTALLED IN RECTANGULAR VALVE BOXES WITH PURPLE LIDS & WITH BALL VALVES ON THE UPSTREAM SIDE.
- M. CONTROL WIRES SHALL BE 14 AWG MIN. SOLID COPPER WIRE, UL APPROVED FOR DIRECT BURIAL, UF TYPE, & WITH 4/64" INSULATION. USE WATERPROOF CONNECTORS AT ALL ELECTRICAL SPLICES & CONNECTIONS - WADE WC-14, 3M DBRY-6, OR RAINBIRD DBRY.
- N. ADJUST SPRINKLER SYSTEM TO PREVENT OVERSPRAY ONTO ADJACENT PAVEMENT OR STRUCTURES. ABOVE GROUND SPRAY EQUIPMENT IS NOT ALLOWED IN PLANTING AREAS 5 FT OR LESS IN WIDTH DIMENSION.
- O. CONTRACTOR SHALL COORDINATE IRRIGATION LINES OR EQUIPMENT TO ACCOMMODATE PLANT MATERIAL INSTALLATION. ADJUST SPRINKLER HEADS TO PROVIDE FULL COVERAGE TO ALL LANDSCAPE AREAS.
- P. VERIFY FINAL LOCATION OF IRRIGATION CONTROLLER WITH OWNER. GENERAL CONTRACTOR SHALL PROVIDE POWER TO CONTROLLER LOCATION. IRRIGATION CONTRACTOR WILL BE RESPONSIBLE FOR COORDINATING HARDWIRING OF THE CONTROLLER.
- Q. A PERMANENT STICKER WITH IRRIGATION CONTRACTOR'S NAME, LICENSE NUMBER, COMPANY NAME, TELEPHONE NUMBER, & WARRANTY PERIOD DATES SHALL BE MOUNTED ON THE IRRIGATION CONTROLLER.
- R. INSTALL WEATHER SENSOR IN A LOCATION THAT IS OPEN TO RAINFALL AND AWAY FROM THE SPRINKLER SPRAY PATTERN.
11. IRRIGATION SYSTEM TESTING
- A. BACKFLOW PREVENTION DEVICE MUST BE TESTED & CERTIFIED BY A CERTIFIED BACKFLOW TESTER. SUBMIT TEST RESULTS TO THE LOCAL WATER PURVEYOR & OWNER WITHIN 10 BUSINESS DAYS OF TESTING.
- B. HYDROSTATIC TESTING OF ALL MAIN LINES & LATERAL LINES ARE REQUIRED. REFER TO THE SPECIFICATIONS FOR PROCEDURES.
- C. ALL VALVE BOX LIDS SHALL BE INSTALLED TO THE PROPER ELEVATIONS.
- D. ENSURE IRRIGATION SYSTEM PROVIDES 100% COVERAGE OF ALL LANDSCAPE AREAS. ADJUST SYSTEM AS NECESSARY.
12. IRRIGATION SYSTEM WARRANTY
- A. CONTRACTOR SHALL GUARANTEE THE IRRIGATION SYSTEM AGAINST ALL DEFECTS OF WORKMANSHIP & MATERIALS FOR A PERIOD OF 1 YEAR FROM DATE OF FINAL ACCEPTANCE.
- B. CONTRACTOR SHALL GUARANTEE ALL BACKFILL AREAS OF TRENCHES FOR A PERIOD OF 1 YEAR FROM DATE OF FINAL ACCEPTANCE.
13. CONTRACTOR SHALL AT ALL TIMES PROTECT NEW WORK FROM DAMAGE & THEFT & REPLACE ALL DAMAGED OR STOLEN MATERIALS AT OWN EXPENSE. CONTRACTOR SHALL PROTECT THE OWNER'S PROPERTY SUCH AS BUILDINGS, UTILITIES, PAVEMENT, TREES, PLANTINGS, ETC. FROM DAMAGE OR LOSS. ALL DAMAGES TO OWNER'S PROPERTY CAUSED BY INSTALLATION WORK SHALL BE REPAIRED AT CONTRACTOR'S COST & TO THE OWNER'S SATISFACTION.
14. CONTRACTOR SHALL REMOVE ALL TRASH & DEBRIS GENERATED DURING CONSTRUCTION. ADJACENT SURFACES SUCH AS ROADS, PAVEMENTS, BUILDING, WALLS, FENCES, ETC. SHALL BE CLEANED OFF IF SOILED BY DIRT OR DEBRIS.
15. REFER TO THE SPECIFICATIONS FOR ALL CLOSEOUT DOCUMENTS & MATERIALS REQUIRED.

- 1 FINISH GRADE AT VALVE BOX: 1/2" AT HYDROMULCH AREAS, 1 1/2" AT SOD AREAS, TOP OF MULCH TO BE FLUSH WITH TOP OF LID AT PLANTING AREAS
- 2 QUICK COUPLING VALVE RAINBIRD-44-NP, 1" INLET, PURPLE LOCKING COVER REQUIRED
- 3 JUMBO VALVE BOX & EXTENSION WITH LOCKING PURPLE LID
- 4 3/4" DIA. WASHED DRAIN GRAVEL
- 5 1" DIA. SCH 80 PVC NIPPLE, LENGTH AS REQUIRED
- 6 BRICK SUPPORTS (4)
- 7 1" DIA. SCH 80 PVC STREET ELL


- 8 #4 REBAR, 24" LENGTH MIN. SECURE TO QUICK COUPLER AT 2 LOCATIONS WITH STAINLESS STEEL TIES.
- 9 1" DIA. SCH 80 PVC TEE OR ELL
- 10 PVC MAIN LINE PIPE
- 11 1" DIA. SCH 80 PVC ELL
- 12 1" SPEARS TRUE-UNION BALL VALVE
- 13 6" DIA. SCH 40 PVC VERTICAL SLEEVE
- 14 WEATHERPROOF TAG WITH FOLLOWING NOTE: "NON-POTABLE WATER-DO NOT DRINK."



QUICK COUPLING VALVE


SCALE: NONE

IRRIGATION SCHEDULE				
SYMBOL	DESCRIPTION	PRODUCT	REMARKS	
IRRIGATION SPRINKLERS				
●●●	ROTOR HEAD - 6" POP-UP	RAINBIRD 5006-PLUS-SAM BODY RAINBIRD 5000 SERIES MPR NOZZLES, FIXED ARC, F,H,Q	USE RADIUS & PATTERN SHOWN ON PLANS. EX. 25H = 25' RADIUS, HALF CIRCLE NOZZLE	
○●●	TURF SPRAY HEAD - 4" POP-UP	RAINBIRD 1804-SAM-PRS SPRAY BODY RAINBIRD MPR NOZZLES, FIXED ARC, F,H,Q	USE RADIUS & PATTERN SHOWN ON PLANS. EX. 15F = 15' RADIUS, FULL CIRCLE NOZZLE	
■	TREE BUBBLERS - 4" POP-UP	RAINBIRD 1804-SAM-PRS SPRAY BODY RB BUBBLER - 1404 FULL CIRCLE, UMBRELLA PATTERN - 1 GPM	INSTALL 2 BUBBLERS FOR LARGE CANOPY TREES & 1 FOR SMALL TREES. INSTALL BUBBLERS ON THE HIGH SIDE OF A SLOPE.	
DRIP EQUIPMENT				
■	DRIPLINES - PLANTING BEDS	NETAFIM - TECHLINE CV - TLCV4-1810 EMITTER SPACING - 18", EMITTER FLOW RATE - .40 GPH	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS. ROW SPACING AT 18" O.C. MAX.	
	DRIP ZONE FUNCTION INDICATOR	RAINBIRD DRIP SYSTEM OPERATION INDICATOR KIT - MODEL # OPERIND	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS IN A LOCATION FURTHEST FROM ZONE VALVE.	
	SUPPLY OR EXHAUST HEADER LINES	CLASS 315 OR CLASS 200 PVC PIPE OR MAY USE 17 MM DRIPLINE BLANK TUBING IF ZONE GPM IS < 5.	SIZE PVC PIPE TO WHERE FLOW DOES NOT EXCEED 5 FEET PER SEC.	
⊕	DRIP REMOTE CONTROL VALVES	NETAFIM - LOW VOLUME CONTROL ZONE KITS WITH VALVES .25 GPM TO 4.4 GPM USE LVCZS805F10075-1F (1" VALVE) 4.5 GPM TO 10 GPM USE LVCZSF10075-HFHP (1" VALVE)	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
IRRIGATION EQUIPMENT				
—	IRRIGATION SLEEVES	ASTM D1785, PVC 1120, SCHEDULE 40 PIPE	SLEEVE SIZE SHALL BE 2 SIZES LARGER THAN THE SIZE OF THE IRRIGATION PIPE(S) TO BE SLEEVED AT THE SLEEVE LOCATION & 4" DIA. MINIMUM.	
1"	LATERAL LINES	ASTM D2241, PVC 1120 OR 1220, SDR 21, CLASS 200 PIPE OR ASTM D2241, PVC 1120 OR 1220, SDR 13.5, CLASS 315 PIPE	USE SIZE SHOWN ON PLANS. 1/2" PIPE - CLASS 315 PIPE; 3/4" & GREATER PIPE - CLASS 200 PIPE	
-----	MAIN LINES	ASTM D2241, PVC 1120, SDR 21, CLASS 200 PIPE	USE SIZE SHOWN ON PLANS.	
⊕	REMOTE CONTROL VALVES	RAINBIRD PEB SERIES REMOTE CONTROL VALVES	USE SIZE SHOWN ON PLANS. INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
●●	BALL VALVES	SPEARS MANUFACTURING TRUE UNION BALL VALVE - TU 2000	SIZE TO MAIN LINE. INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
⊕	QUICK COUPLING VALVES	RAINBIRD 44-NP (1" INLET W/ PURPLE LOCKING COVER) 44-K (VALVE KEY), SH-2 (HOSE SWIVELS), 2049 COVER KEY	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
⊕	MASTER CONTROL VALVE	IRRITROL 700 -1 (NORMALLY OPEN), 700 SERIES ULTRAFLOW	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
⊕	RP BACKFLOW PREVENTION DEVICE	1" ZURN WILKINS 975XLU REDUCED PRESSURE PRINCIPLE ASSEMBLY WITH UNION BALL VALVES	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
	BACKFLOW ENCLOSURE	GORILLA CAGE - GORILLA MANUFACTURING 281-705-9701	SELECT PROPER SIZE FOR BACKFLOW DEVICE, GREEN COLOR	
	BACKFLOW FREEZE PROTECTION BLANKET	INSULATION POUCH - DEKORRA PRODUCTS 1-888-635-8585	SELECT PROPER SIZE FOR BACKFLOW DEVICE, GREEN COLOR	
⊕	PRESSURE REDUCING VALVE	1" ZURN WILKINS 500 XL-SC PRESSURE REDUCING VALVE WITH SEALED CAGE BELL HOUSING & STAINLESS STEEL SCREW	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
⊕	ISOLATION GATE VALVE	1" NIBCO T-113 BRONZE GATE VALVE	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS.	
⊕	WATER METER	BY OTHERS. REFER TO CIVIL PLANS.	COORDINATE WITH GENERAL CONTRACTOR.	
⊕	IRRIGATION CONTROLLER	WEATHERMATIC - SL1600	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS. VERIFY FINAL LOCATION WITH OWNER.	
⊕	WEATHER STATION	WEATHERMATIC WIRELESS WEATHER STATION MODEL - SLWS	INSTALL PER MANUFACTURER'S SPECIFICATIONS & INSTRUCTIONS. INSTALL SENSOR AWAY FROM SPRINKLER SPRAY PATTERN.	
ZONE TYPE T=TURF B=TREE BUBBLER R=ROTOR ZONE NUMBER				
VALVE SIZE 1 1/2" 30.0				
ZONE GPM				
ZONE NUMBER (DRIP ZONES)				
5" VALVE SIZE 3.0				
ZONE GPM				



IRRIGATION WATERING SCHEDULE


		ZONE NUMBER												TOTAL RUN TIME (HR/WK)	
		ZONE TYPE													
		PRECIPITATION RATE (IN/HR)													
MONTH ET	ADJUST ET	ADJUST %		1.52	1.52	1.58	0.61	0.63	0.60	3.85	3.85	3.85	0.30	0.30	
JANUARY 2.42	1.45	33%	WATER (IN/WK)	.33	.33	.33	.33	.33	.33	.33	.33	.33	.33	.33	4.78
			TIME (MIN/WK)	13	13	13	33	32	33	6	6	6	66	66	
FEBRUARY 2.90	1.74	40%	WATER (IN/WK)	.44	.44	.44	.44	.44	.44	.44	.44	.44	.44	.44	6.28
			TIME (MIN/WK)	18	18	17	43	42	44	7	7	7	87	87	
MARCH 4.42	2.65	60%	WATER (IN/WK)	.60	.60	.60	.60	.60	.60	.60	.60	.60	.60	.60	8.63
			TIME (MIN/WK)	24	24	23	59	58	60	10	10	10	120	120	
APRIL 5.47	3.28	75%	WATER (IN/WK)	.77	.77	.77	.77	.77	.77	.77	.77	.77	.77	.77	11.03
			TIME (MIN/WK)	31	31	30	76	73	77	12	12	12	154	154	
MAY 6.47	3.88	88%	WATER (IN/WK)	.88	.88	.88	.88	.88	.88	.88	.88	.88	.88	.88	12.62
			TIME (MIN/WK)	35	35	34	87	84	88	14	14	14	176	176	
JUNE 6.97	4.18	95%	WATER (IN/WK)	.98	.98	.98	.98	.98	.98	.98	.98	.98	.98	.98	14.05
			TIME (MIN/WK)	39	39	38	96	93	98	16	16	16	196	196	
JULY 7.31	4.39	100%	WATER (IN/WK)	.99	.99	.99	.99	.99	.99	.99	.99	.99	.99	.99	14.28
			TIME (MIN/WK)	40	40	38	98	95	100	16	16	16	199	199	
AUGUST 6.99	4.19	95%	WATER (IN/WK)	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	.95	13.62
			TIME (MIN/WK)	38	38	36	94	91	95	15	15	15	190	190	
SEPTEMBER 5.64	3.38	77%	WATER (IN/WK)	.79	.79	.79	.79	.79	.79	.79	.79	.79	.79	.79	11.37
			TIME (MIN/WK)	32	32	30	78	76	79	13	13	13	158	158	
OCTOBER 4.44	2.66	61%	WATER (IN/WK)	.60	.60	.60	.60	.60	.60	.60	.60	.60	.60	.60	8.70
			TIME (MIN/WK)	24	24	23	60	58	61	10	10	10	121	121	
NOVEMBER 2.85	1.71	39%	WATER (IN/WK)	.40	.40	.40	.40	.40	.40	.40	.40	.40	.40	.40	5.78
			TIME (MIN/WK)	16	16	16	40	38	40	7	7	7	80	80	
DECEMBER 2.36	1.42	32%	WATER (IN/WK)	.32	.32	.32	.32	.32	.32	.32	.32	.32	.32	.32	4.62
			TIME (MIN/WK)	13	13	13	32	31	32	5	5	5	64	64	
NOTES:															
1. REFER TO THE LOCAL CITY ORDINANCE FOR ALLOWABLE NUMBER OF WATERING DAYS.															
2. TO MINIMIZE RUNOFF, DIVIDE WATERING TIME & USE MULTIPLE CYCLES.															
3. IRRIGATION WATERING SCHEDULE IS PROVIDED TO THE CONTRACTOR/OWNER AS A REFERENCE ONLY TO WATER ESTABLISHED PLANT MATERIAL. CONTRACTOR/OWNER SHALL FIELD OBSERVE & ADJUST SCHEDULE AS REQUIRED FOR PLANT ESTABLISHMENT, FUTURE PLANT WATER NEEDS, MICRO-CLIMATE CONDITIONS, & VARIATIONS IN SEASONAL WEATHER.															



ISOLATION GATE VALVE

SCALE: NONE

- 1 REDUCED PRESSURE PRINCIPLE BACKFLOW DEVICE - ZURN WILKINS 975XLU WITH 2 UNION BALL VALVES
- 2 12" MIN. & 30" MAX. ABOVE GRADE
- 3 CONCRETE PAD ON 4" AGGREGATE BASE COMPACTED TO 95% O.D.
- 4 IRRIGATION MAIN LINE
- 5 COPPER PIPE FROM WATER METER
- 6 TYPE K COPPER PIPE & FITTINGS. MUST COMPLY WITH LOCAL CODES.
- 7 PROVIDE COPPER UNION
- 8 4" DIA. MIN. SCH 40 PVC SLEEVE (TYP.)
- 9 ENCLOSURE & RP FREEZE PROTECTION BLANKET
1. INSTALL BACKFLOW PREVENTER TO MEET ALL LOCAL CODES & TCEQ STANDARDS.
2. PERFORM BACKFLOW TEST BY A CERTIFIED TESTER AFTER INSTALLATION.



RP BACKFLOW PREVENTER

SCALE: NONE

- 1 VALVE BOX WITH EXTENSION & LID
- 2 FINISH GRADE
- 3 MASTER CONTROL VALVE - IRRITROL 700 SERIES
- 4 WATERPROOF CONNECTORS (2) WADE WC-14, 3M DBRY-6, OR RAINBIRD DBRY
- 5 24" LENGTH MIN. COILED WIRE
- 6 PVC SCH 80 MALE ADAPTER
- 7 PVC MAIN LINE PIPE
- 8 BRICK SUPPORTS (4 TOTAL)
- 9 4" DEPTH MIN. 3/4" WASHED DRAIN GRAVEL
- 10 VALVE ID TAG
- FINISH GRADE AT TOP OF VALVE BOX LID: 1/2" IN HYDROMULCH AREAS, 1 1/2" IN SOD AREAS, FLUSH WITH TOP OF MULCH IN PLANTING AREAS

MASTER CONTROL VALVE

SCALE: NONE

- 1 VALVE BOX WITH LID & VALVE BOX EXTENSION AS REQUIRED
- 2 FINISH GRADE AT VALVE BOX
- 3 REMOTE CONTROL VALVE RAINBIRD PEB SERIES
- 4 WATERPROOF CONNECTORS (2) WADE WC-14, 3M DBRY-6, OR RAINBIRD DBRY
- 5 24" LENGTH MIN. COILED WIRE
- 6 SCH 80 PVC T.O.E. NIPPLE
- 7 PVC MAIN LINE PIPE & FITTINGS
- 8 BRICK SUPPORTS (4)
- 9 4" DEPTH MIN. 3/4" DIA. WASHED DRAIN GRAVEL
- 10 VALVE ID TAG
- 11 LATERAL LINE & FITTINGS
- FINISH GRADE AT TOP OF VALVE BOX LID: 1/2" IN HYDROMULCH AREAS, 1 1/2" IN SOD AREAS, FLUSH WITH TOP OF MULCH IN PLANTING AREAS

REMOTE CONTROL VALVE

SCALE: NONE

© 2018 PLACE MATRIX DESIGN OFFICE, LLC
ALL RIGHTS RESERVED. DOCUMENT MAY NOT BE REPRODUCED, COPIED, EDITED, OR PUBLISHED IN ANY FORMAT WITHOUT PRIOR WRITTEN PERMISSION OF PLACE MATRIX DESIGN OFFICE, LLC.



PROJECT NAME

BANDERA RETAIL CENTER
7706 BANDERA ROAD
SAN ANTONIO, TX 78238

PROJECT INFO.

PROJECT NUMBER: 201803

DRAWN BY: ISP

CHECKED BY: ISP

ISSUE DATE

04-16-2018

REVISIONS


NUM	DATE	DESCRIPTION	CITY REVIEW COMMENTS
1	10-02-2018		

SHEET TITLE


IRRIGATION
DETAILS

SHEET NUMBER







A SPRAY HEAD (TYP.)
SCALE: NONE




B ROTOR HEAD (TYP.)
SCALE: NONE




C TREE BUBBLERS
SCALE: NONE



D IRRIGATION CONTROLLER & WEATHER SENSOR
SCALE: NONE





E PRESSURE REDUCING VALVE
SCALE: NONE




F DRIP ZONE INSTALLATION - PLAN (TYP.)
SCALE: NONE


1. REMOTE CONTROL VALVE WITH SCREEN FILTER & PRESSURE REDUCING VALVE
2. DRIPLINE START CONNECTION
3. CLASS 200 PVC SUPPLY HEADER, MAY USE DRIPLINE BLANK TUBING IF ZONE FLOW IS < 5 GPM.
4. SEE PLANS TO DETERMINE ROW SPACING.
5. PERIMETER LATERALS, 4" FROM EDGE OF PAVEMENT OR BEDS
6. NETAFIM TECHLINE® CV DRIPLINE
7. EDGE OF PLANTING AREA
8. CLASS 200 PVC EXHAUST HEADER, MAY USE DRIPLINE BLANK TUBING IF ZONE FLOW IS < 5 GPM.
9. MANUAL FLUSH VALVE PLUMBED TO PVC
10. INSTALL 6" SOIL STAPLES EVERY 4 FT. MAX. & ALSO BEFORE & AFTER EVERY TURN.
11. TECHLINE TEE (TYP.)
12. ZONE FUNCTION INDICATOR
- NOTES:
1. RECOMMENDED MIN. FILTRATION: 120 MESH
2. PRESSURE AT FLUSH VALVE SHALL BE MIN. 21.8 PSI




G DRIP ZONE INSTALLATION - SECTION (TYP.)
SCALE: NONE




H DRIP CONTROL ZONE KIT
SCALE: NONE




I DRIP ZONE - MANUAL FLUSH VALVE
SCALE: NONE




J DRIP ZONE - FUNCTION INDICATOR
SCALE: NONE



K IRRIGATION TRENCH (TYP.)
SCALE: NONE




L IRRIGATION SLEEVES (TYP.)
SCALE: NONE



M VALVE BOX LAYOUT (TYP.)
SCALE: NONE

- NOTES:
1. NEATLY ALIGN VALVE BOXES TO EACH OTHER & TO THE EDGE.
2. INSTALL VALVE BOXES IN SHRUB PLANTING AREAS WHENEVER POSSIBLE.

COSA TREE CANOPY REQUIREMENT CALCULATIONS		COSA LANDSCAPE ORDINANCE POINTS TABULATION		COSA PARKING LOT SHADING REQUIREMENT CALCULATIONS	
A. TOTAL SITE AREA = 46,550 SF		ELECTIVE REQUIREMENTS - 70 POINTS		A. TOTAL PARKING LOT AREA = 12,307 SF	
25% OF SITE AREA = 11,637.50 SF		B. PARKING LOT SHADING		PARKING LOT PERCENT SHADING = 25%	
B. TREE CANOPY COVERAGE REQUIRED		PERCENT SHADING - 25%		SHADE COVERAGE REQUIRED = 3,076.75 SF	
CANOPY COVERAGE REQUIRED = 11,637.50 SF		C. SCREENING OF SURFACE PARKING		B. MEDIUM-LARGE TREE - DENOTED ON PLAN BY PT	
C. NEW TREE CANOPY COVERAGE		BANDERA RD. - 225 LF X 75% / 50 = 4 TREES REQUIRED		ISLAND OR PENINSULA TREE	
LARGE TREE		WESTCHASE ST. - 207 LF X 75% / 50 = 4 TREES REQUIRED		656.25 SF X 3 TREE(S) = 1968.75 SF	
4 X 1080 = 4,320 SF		TOTAL ELECTIVE POINTS		WITHIN 12 FT. OF PARKING LOT	
MEDIUM - LARGE TREE		70 POINTS		437.50 SF X 1 TREE(S) = 437.50 SF	
10 X 787.50 = 7,875 SF		BUFFER TYPE B (OPTION 2) - 15 FT WIDE		C. SMALL TREE - DENOTED ON PLAN BY PT	
TOTAL NEW CANOPY COVERAGE PROVIDED = 12,195 SF		BANDERA RD. - 225 LF		ISLAND OR PENINSULA TREE	
D. TOTAL TREE CANOPY COVERAGE		2 CANOPY TREES / 100 LF = 5 TREES		206.25 SF X 4 TREE(S) = 825 SF	
12,195 SF NEW TREES		2 SMALL TREES / 100 LF = 5 TREES		TOTAL PARKING LOT SHADING = 3,231.25 SF	
TOTAL TREE CANOPY COVERAGE = 12,195 SF		6 LG SHRUBS / 100 LF		PERCENT OF PARKING LOT SHADING = 26%	
26% TREE CANOPY COVERAGE PROVIDED		8 MED SHRUBS / 100 LF			
		6 SMALL SHRUBS / 100 LF			



PLANT SCHEDULE							
SYMBOL	KEY	QTY	BOTANICAL NAME COMMON NAME	SIZE	HEIGHT/ SPREAD	SPACING	REMARKS
CANOPY TREES							
⊕	QP	5	QUERCUS POLYMORPHA MEXICAN WHITE OAK	3" CAL., 65 GAL	10' - 12' HT. 5' - 6' SPREAD	PER PLAN	CONTAINER GROWN, SINGLE TRUNK, MATCHED SPECIMEN
⊙	QS	4	QUERCUS SHUMARDII SHUMARD RED OAK	3" CAL., 65 GAL	12' - 14' HT. 6' - 8' SPREAD	PER PLAN	CONTAINER GROWN, SINGLE TRUNK, MATCHED SPECIMEN
⊗	QV	3	QUERCUS VIRGINIANA LIVE OAK	2 1/2" CAL., 30 GAL	10' - 12' HT. 4' - 5' SPREAD	PER PLAN	CONTAINER GROWN, SINGLE TRUNK, MATCHED SPECIMEN
⊖	UC	5	ULMUS CRASSIFOLIA CEDAR ELM	3" CAL., 65 GAL	10' - 12' HT. 4' - 5' SPREAD	PER PLAN	CONTAINER GROWN, SINGLE TRUNK, MATCHED SPECIMEN
ORNAMENTAL / SMALL TREES							
⊙	IV	4	ILEX VOMITORIA YAUPOH HOLLY	30 GAL.	6' - 7' HT. 3' - 4' SPREAD	PER PLAN	CONTAINER GROWN, MULTI-TRUNK, MATCHED SPECIMEN, FEMALE TREE
⊙	SS	5	SOPHORA SECUNDIFLORA TEXAS MOUNTAIN LAUREL	30 GAL.	6' HT. 3' - 4' SPREAD	PER PLAN	CONTAINER GROWN, MULTI-TRUNK, MATCHED SPECIMEN
SHRUBS, GROUND COVER, ORNAMENTAL GRASSES							
⊕	CAE	13	CAESALPINIA PULCHERRIMA PRIDE OF BARBADOS	5 GAL.	-	6" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊖	DBC	61	DIETES BICOLOR FORTNIGHT LILY	3 GAL.	-	42" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊗	HPP	77	HEPERALOE PARVIFLORA 'PERPA' BRAKELIGHTS RED YUCCA	1 GAL.	-	36" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊕	IVN	20	ILEX VOMITORIA 'NANA' DWARF YAUPOH HOLLY	3 GAL.	-	36" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊙	MCP	59	MUHLENBERGIA CAPILLARIS GULF MUHLY GRASS	1 GAL.	-	42" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊖	PLM	47	PLUMBAGO AURICULATA PLUMBAGO	3 GAL.	-	48" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊙	RMG	22	ROSA 'MARTHA GONZALES' MARTHA GONZALES ROSE	3 GAL.	-	42" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
⊕	SGR	18	SALVIA GREGGII 'WHITE' CHERRY SAGE	1 GAL.	-	42" O.C.	CONTAINER GROWN, MATCHED SPECIMEN, FULL
TURF GRASS							
⊖	GRASS	-	CYNODON DACTYLON BERMUDA GRASS	-	-	-	HYDROMULCH
COBBLE							
⊖	COBBLE	-	GRANITE BAY - 6" - 12" DIA. AT 12" DEPTH MIN. SOURCE: KELLER MATERIAL - 210-967-1300	-	-	-	INSTALL FILTER FABRIC UNDER ROCK MATERIAL.

- GENERAL NOTES:
1. REFER TO CIVIL PLANS FOR GRADING, DRAINAGE, & UTILITIES INFORMATION.
 2. REFER TO CIVIL PLANS FOR RETAINING WALL INFORMATION.
 3. REFER TO MEP PLANS FOR SITE LIGHTING & ELECTRICAL INFORMATION.
 4. REFER TO THE IRRIGATION PLANS FOR SLEEVE LOCATIONS.
 5. PROVIDE A 4" DEPTH MIN. OF TOPSOIL AT ALL NEW GRASS AREAS.
 6. GRASS IN DRAINAGE EASEMENT & R.O.W. AREAS DISTURBED BY CONSTRUCTION ACTIVITIES MUST BE REPAIRED.

LANDSCAPE INSPECTION
REQUIRED
CALL: 207-1111

DATE 10/18
BY [Signature]

THIS SET OF PLANS AND SPECIFICATIONS **MUST** BE KEPT ON THE JOB AT ALL TIMES. OTHERWISE THE JOB IS SUBJECT TO REJECTION IT IS UNLAWFUL TO MAKE ANY CHANGES OR ALTERATIONS ON SAME WITHOUT WRITTEN PERMISSION FROM THE BUILDING INSPECTOR'S OFFICE. CITY OF SAN ANTONIO THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW.

LANDSCAPE PLAN

SCALE: 1" = 20'-0"

10 0 20 40 FEET

NORTH

TEXAS 811

Know what's below.
Call before you dig.

Rev. 10/09/18

PLACE MATRIX
DESIGN OFFICE, LLC
PO BOX 41107 - AUSTIN, TX 78704
TEL: 512-559-4095
info@placematrixdesign.com

SEAL
REGISTERED LANDSCAPE ARCHITECT
STATE OF TEXAS
2639
10-02-2018

PROJECT NAME
BANDERA RETAIL CENTER
7706 BANDERA ROAD
SAN ANTONIO, TX 78238

PROJECT INFO.

PROJECT NUMBER: 201803

DRAWN BY: ISP

CHECKED BY: ISP

ISSUE DATE
04-16-2018

REVISIONS

NUM	DATE	DESCRIPTION
1	10-02-2018	CITY REVIEW COMMENTS

SHEET TITLE
LANDSCAPE PLAN

SHEET NUMBER
20

© 2018 PLACE MATRIX DESIGN OFFICE, LLC
ALL RIGHTS RESERVED. DOCUMENT MAY
NOT BE REPRODUCED, COPIED, EDITED, OR
PUBLISHED IN ANY FORMAT WITHOUT
PRIOR WRITTEN PERMISSION OF
PLACE MATRIX DESIGN OFFICE, LLC.

THESE NOTES SHALL BE USED IN ASSOCIATION WITH SPECIFICATION SECTION 32 93 00 ON PLANTING & THE DRAWING DETAILS.

2. PERFORM ALL WORK IN ACCORDANCE WITH ALL APPLICABLE LAWS, CODES, AND REGULATIONS REQUIRED BY AUTHORITIES HAVING JURISDICTION OVER SUCH WORK AND PROVIDE FOR ALL INSPECTIONS AND PERMITS REQUIRED BY FEDERAL, STATE, AND LOCAL AUTHORITIES IN SUPPLY, TRANSPORTATION, AND INSTALLATION OF MATERIALS.

3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERIFICATION OF ALL EXISTING UNDERGROUND UTILITY LINES (TELEPHONE, GAS, WATER, ELECTRICAL, CABLE, TV, ETC.) AND ANY EASEMENTS OR AERIAL EASEMENTS PRIOR TO START OF ANY LANDSCAPE & SITE WORK. CONTACT TEXAS ONE CALL & OTHERS AT LEAST 48 HOURS PRIOR TO START OF ANY SITE WORK. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES TO EXISTING UTILITIES.

4. CONTRACTOR SHALL REFER ALSO TO THE CIVIL / MEP PLANS FOR ALL PROPOSED SITE UTILITY & SITE GRADING WORK INFORMATION.

5. CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS SHOWN ON THE PLANS. IF A SITE CONFLICT IS PRESENT, THEN THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT PRIOR TO BEGINNING ANY SITE LANDSCAPE WORK.

6. ALL SITE GRADING, IRRIGATION INSTALLATION, & HARD SURFACE PAVING ADJACENT TO PLANTING AREAS, INCLUDING CONCRETE WALKS & ROAD WORK, MUST BE COMPLETED PRIOR TO START OF ANY PLANTING WORK ACTIVITY. CONTRACTOR WILL BE RESPONSIBLE FOR ADJUSTING ELEVATIONS OF NEW TREES & PLANTING BEDS IF INSTALLED AT IMPROPER ELEVATIONS.

7. CONTRACTOR SHALL COORDINATE ALL LANDSCAPE INSTALLATION WORK WITH OTHER TRADES TO PREVENT ANY WORK CONFLICTS.

8. TREE PLANTING

A. ANY SUBSTITUTIONS TO TREE SPECIES OR SPECS. IN THE PLANT SCHEDULE WILL NOT BE PERMITTED UNLESS APPROVAL IS OBTAINED IN WRITING FROM THE LANDSCAPE ARCHITECT.

B. FOR TREE PLANTING, REFER TO THE TREE PLANTING DETAILS & PLANTING SPECIFICATIONS.

C. ENSURE PROPER DRAINAGE IN TREE PITS BY PERFORMING A DRAINAGE TEST. FILL PIT WITH WATER & ALLOW TO DRAIN TWICE IN SUCCESSION. IF PIT DOES NOT SUFFICIENTLY DRAIN WITHIN 24 HOURS, REFER TO THE SPECIFICATIONS FOR DIRECTION OR CONTACT THE LANDSCAPE ARCHITECT.

D. STAIN TREES PER DRAWING DETAIL. TREE SUPPORT SYSTEMS SHALL BE REMOVED AFTER 1 YEAR IF TREE ROOT SYSTEM IS ESTABLISHED.

9. SHRUB PLANTING

A. ANY SUBSTITUTIONS TO SHRUB SPECIES OR SPECS. IN THE PLANT SCHEDULE WILL NOT BE PERMITTED UNLESS APPROVAL IS OBTAINED IN WRITING FROM THE LANDSCAPE ARCHITECT.

B. FOR SHRUB PLANTING, REFER TO THE SHRUB PLANTING DETAILS & PLANTING SPECIFICATIONS.

C. FOR SHRUB PLANTING IN MASS PLANTING BEDS, EXCAVATE TO A MINIMUM DEPTH OF 8" FOR PLANTING SOIL PLUS A DEPTH OF 3" TO ACCOMMODATE THE MULCH LAYER. PRIOR TO PLACING PLANTING SOIL MIX, LOOSEN THE SUBGRADE TO A DEPTH OF 4 INCHES OR TO 6 INCHES IF SOIL IS COMPACTED.

D. TEST ALL PLANTING BEDS TO ENSURE PROPER DRAINAGE. ALLOW TO DRAIN FOR 24 HOURS. IF BEDS DO NOT DRAIN SUFFICIENTLY, REFER TO THE SPECIFICATIONS FOR DIRECTION OR CONTACT THE LANDSCAPE ARCHITECT.

E. PROVIDE PLANTING SOIL MIX & MULCH ACCORDING TO THE DRAWING DETAILS & SPECIFICATIONS. INSTALL SHRUBS IN MASS PLANTING BEDS WITH A TRIANGULAR SPACING PATTERN.

F. CONTRACTOR IS RESPONSIBLE FOR FINE GRADING AT ALL PLANTING BEDS. PRIOR TO PLANTING, ENSURE THAT THE BEDS WITH NEW SOIL MIX ARE ESTABLISHED AT THE PROPER GRADES. REMOVE ALL DEBRIS, LUMPS, & ROCK. FINISH SURFACE SHALL BE SMOOTH, EVEN, & FREE OF DEPRESSIONS THAT CAN CAUSE WATER TO POND.

G. FINISH SOIL SURFACE PLUS MULCH LAYER SHALL NOT BE LOWER THAN 1 INCH BELOW ALL PAVING OR CURB SURFACES AFTER SETTLEMENT.

10. MULCHING

A. APPLY A 4" MIN. DEPTH OF HARDWOOD MULCH TO ALL PLANTING BEDS. APPLY A 4" MIN. DEPTH OF HARDWOOD MULCH TO ALL SOIL WATERING SAUCERS FOR TREES.

B. DO NOT PLACE MULCH WITHIN 6" OF TREE TRUNKS & 3" OF SHRUB STEMS. AVOID PLACING SOIL OR MULCH ON TOP OF PLANT ROOT BALLS. ALLOW NO MORE THAN 1" DEPTH OF MULCH OVER THE TOP OF PLANT ROOT BALLS.

C. FINISH SURFACE OF SETTLED MULCH SHALL BE NO MORE THAN 1" BELOW ADJACENT PAVEMENT OR CURB SURFACES & 1/2" BELOW TOP OF ANY LANDSCAPE EDGING.

11. SATISFACTORY FINE GRADING

A. ENSURE THAT THE PROPER GRADES & ELEVATIONS AT ALL PLANTING AREAS ARE ESTABLISHED. REFER TO THE CIVIL GRADING PLANS FOR PROPER FINISH ELEVATIONS REQUIRED.

B. ENSURE THAT POSITIVE SURFACE DRAINAGE AWAY FROM BUILDINGS & STRUCTURES IS ESTABLISHED.

12. PLANT MATERIAL WARRANTY & MAINTENANCE PERIOD

A. WARRANTY PERIOD: ALL PLANT MATERIAL, RELATED MATERIALS, & WORK SHALL BE GUARANTEED & WARRANTED FOR A PERIOD OF 12 MONTHS AFTER THE DATE OF FINAL COMPLETION.


B. MAINTENANCE PERIOD: ALL PLANT MATERIAL & RELATED WORK SHALL BE MAINTAINED FOR A PERIOD OF 90 DAYS AFTER THE DATE OF FINAL COMPLETION.

C. ALL PLANTING & ASSOCIATED WORK SHALL BE MAINTAINED IN A HEALTHY OR GOOD CONDITION. DURING THIS TIME PERIOD, ANY PLANTS DETERMINED TO BE DEAD OR DYING SHALL BE REMOVED & REPLACED.

13. ALL DISTURBED AREAS CAUSED BY GRADING OR CONSTRUCTION ACTIVITIES BOTH ON & OFF PROPERTY SHALL BE GRASS HYDROMULCHED.


14. CONTRACTOR SHALL AT ALL TIMES PROTECT NEW WORK FROM DAMAGE & THEFT & REPLACE ALL DAMAGED OR STOLEN MATERIALS AT OWN EXPENSE. CONTRACTOR SHALL PROTECT THE OWNER'S PROPERTY SUCH AS BUILDINGS, UTILITIES, PAVEMENT, TREES, PLANTINGS, ETC. FROM DAMAGE OR LOSS. ALL DAMAGES TO OWNER'S PROPERTY CAUSED BY INSTALLATION WORK SHALL BE REPAIRED AT CONTRACTOR'S COST & TO THE OWNER'S SATISFACTION.

15. CONTRACTOR SHALL REMOVE ALL TRASH & DEBRIS GENERATED DURING CONSTRUCTION. ADJACENT SURFACES SUCH AS ROADS, PAVEMENTS, BUILDING, WALLS, FENCES, ETC. SHALL BE CLEANED OFF IF SOILED BY DIRT, DEBRIS, OR GRASS OPERATIONS.



(C) TREE PLANTING ON SLOPE
SCALE: NONE

1. THESE NOTES SHALL BE USED IN ASSOCIATION WITH SPECIFICATION SECTION 32 92 00 ON TURF & GRASSES.
2. REFER TO ITEMS 2 THRU 5 OF THE PLANTING NOTES FOR GENERAL REQUIREMENTS.
3. ALL SITE GRADING, IRRIGATION INSTALLATION, & HARD SURFACE PAVING ADJACENT TO PLANTING AREAS, INCLUDING CONCRETE WALKS & ROAD WORK, MUST BE COMPLETED PRIOR TO START OF ANY GRASS WORK. CONTRACTOR WILL BE RESPONSIBLE FOR FINAL GRADING OF NEW GRASS AREAS TO THE PROPER GRADES. IMPROPER ELEVATIONS SHALL BE CORRECTED AT OWN COST.
4. CONTRACTOR SHALL COORDINATE ALL GRASS WORK WITH OTHER TRADES TO PREVENT ANY WORK CONFLICTS.
5. GRASS HYDROSEED (HYDROMULCH)
 - A. ALL GRASS SEED SHALL BE FRESH, CLEAN, DRY, NEW CROP SEED WITH MIN. 85% PURITY, MIN. 90% GERMINATION, & NOT MORE THAN 0.5% WEED SEED.
 - B. GRASS SEED SHALL BE DELIVERED IN UNDAMAGED, UNOPENED CONTAINERS & BE DRY & FREE OF MOLD.
 - C. GRASS SEED MIX:
 - BERMUDA GRASS (*Cynodon dactylon*) SEED
 - APPLICATION RATE: 2 LBS. PER 1,000 SF
 - WINTER MIX (FROM SEPTEMBER 15 TO MARCH 1):
 - BERMUDA GRASS (*Cynodon dactylon*) SEED
 - APPLICATION RATE: 2 LBS. PER 1,000 SF
 - ANNUAL RYE (*Lolium multiflorum*) GRASS SEED
 - APPLICATION RATE: 6 LBS. PER 1,000 SF
 - D. FIBER MULCH:
 - CELLULOSE FIBER MULCH - MINIMUM 2,000 LB / ACRE
6. GRASS HYDROSEED WORK
 - A. ALL AREAS TO RECEIVE GRASS SHALL HAVE A 4" DEPTH MIN. LAYER OF TOPSOIL PLACED OVER SUBGRADE. INSTALL TOPSOIL TO 1/2" BELOW TOP OF PAVEMENT, CURBS, OR METAL EDGER. LOOSEN SUBGRADE TO 4" OR TO 6" IF SOIL IS COMPACTED, PRIOR TO SPREADING TOPSOIL.
 - B. CONTRACTOR IS RESPONSIBLE FOR FINE GRADING AT ALL GRASS AREAS. PRIOR TO GRASS WORK, REMOVE ALL DEBRIS, LUMPS, & ROCK GREATER THAN 1 INCH IN DIAMETER. FINISHED SURFACE SHALL BE SMOOTH, EVEN, & FREE OF DEPRESSIONS THAT CAN CAUSE WATER TO POND. REFER TO THE CIVIL GRADING PLANS FOR FINAL GRADES REQUIRED. ENSURE THAT POSITIVE SURFACE DRAINAGE AWAY FROM BUILDINGS & STRUCTURES IS ESTABLISHED.
 - C. APPLY HYDROSEED SLURRY UNIFORMLY TO ALL AREAS TO BE SEEDED. REMOVE OVER-SPRAYED SLURRY MIX FROM ADJACENT PLANTS & STRUCTURES.
 - D. FOLLOWING GERMINATION OF THE SEED, AREAS LACKING GERMINATION LARGER THAN 8" X 8" MUST BE RE-SEEDED.
7. MAINTENANCE
 - A. MAINTENANCE OF SEEDED AREAS SHALL BEGIN UPON COMPLETION OF SEEDING OPERATION & CONTINUE UNTIL FULL GRASS ESTABLISHMENT.
 - B. MAINTENANCE SHALL INCLUDE WATERING, WEEDING, MOWING, TRIMMING, EDGING, FERTILIZING, RE-SEEDING, & PERFORMING OTHER OPERATIONS AS REQUIRED TO ESTABLISH HEALTHY, VIABLE TURF.
8. GRASS WORK MAINTENANCE PERIOD
 - A. MAINTENANCE PERIOD: ALL GRASS WORK SHALL BE MAINTAINED FOR A PERIOD OF 90 DAYS AFTER THE DATE OF FINAL COMPLETION. GRASS SHALL BE MAINTAINED IN A HEALTHY CONDITION. DURING THIS TIME PERIOD, ANY GRASS AREAS DETERMINED TO BE BARE, DEAD, OR DYING SHALL BE REMOVED & RE-SEEDED.
 - B. FOR ALL SEEDED GRASS AREAS, ESTABLISHMENT BY THE END OF THE MAINTENANCE PERIOD IS DEFINED AS A HEALTHY, UNIFORM STAND OF GRASS, FREE OF WEED GROWTH & SURFACE IRREGULARITIES, WITH COVERAGE EXCEEDING 90% OVER ANY 10 SF & BARE SPOTS NOT EXCEEDING 5" X 5". IF GRASS IS NOT CONSIDERED ESTABLISHED, THEN THE MAINTENANCE PERIOD SHALL BE EXTENDED UNTIL FULL ESTABLISHMENT. BARE SPOTS SHALL BE RE-SEEDED WHERE NECESSARY.



NOTES:

1. FOR TREE PLANTING, REFER ALSO TO THE PLANTING SPECIFICATIONS.
2. PIT SIZE: EXCAVATE CIRCULAR PIT WITH TAPERED SIDES. EXCAVATE MIN. 3X ROOT BALL WIDTH AT SURFACE & TAPER DOWN TO 2X ROOT BALL WIDTH AT BOTTOM.
3. TOP OF ROOT BALL & ROOT FLARE SHOULD BE FLUSH OR NO HIGHER THAN 2" ABOVE FINISH GRADE.
4. BACKFILL SOIL MIX: 6 PARTS NATIVE SOIL FROM EXCAVATED PIT OR IMPORTED TOPSOIL, 2 PARTS COMPOST, 1 PART COARSE SAND.
5. FERTILIZER: DAVEY ARBOR GREEN PRO 30-10-7 PACKETS. APPLY PER MANUFACTURER'S DIRECTIONS.
6. MULCH: APPROVED UNTREATED HARDWOOD MULCH PER SPECIFICATIONS.
7. KEEP MULCH 6" MIN. CLEAR FROM THE TREE TRUNK & ROOT FLARE AREA.
8. TEST ALL TREE PITS FOR PROPER DRAINAGE. REFER TO PLANTING SPECIFICATIONS.
9. REMOVE NURSERY BAMBOO POLE STAKES UNLESS CENTRAL LEADER NEEDS TO BE HELD ERECT. REMOVE ALL NURSERY TAGS & TREE RIBBONS.

Diagram illustrating Triangular Plant Spacing. The diagram shows a grid of circles (plants) arranged in a triangular pattern. Dimensions are labeled: 'X' PLANT SPACING (horizontal distance between plants in a row), 'Y' PLANT SPACING (vertical distance between rows), and a 60° angle. A note indicates '6" EDGE OF CURBS, PAVING, EDGER, WALL, BUILDING, ETC.'.

'X' PLANT SPACING	'Y'
6"	5"
8"	7"
12"	10 1/2"
18"	15 1/2"
24"	21"
30"	26"
36"	31"
42"	36 1/2"
48"	41 1/2"
5'	52"
6'	62"

TRIANGULAR PLANT SPACING
REFER TO PLANT SCHEDULE FOR 'X' PLANT SPACING.

1/8" X 4" STEEL EDGE WITH MIN. 12" DEEP STAKES, COLOR - GREEN

TURF GRASS

FINISH GRADE, 1 1/2" BELOW TOP OF STEEL EDGE

PLANTING BED MULCH, TAPER MULCH TO BE 1/2" BELOW TOP OF STEEL EDGE.

PLANTING BED SOIL MIX

SUBGRADE

① ACCEPTABLE STEEL EDGE MANUFACTURERS:
COLMET - 1.800.829.8225
1/8" X 4" ITEM #1011
J.D. RUSSELL CO. - 1.800.888.6872
1/8" X 4" DURAEDGE

E STEEL EDGE
SCALE: NONE



- C. Water plants immediately after planting. If for any reason the irrigation system cannot run, hand water all plants by means of a hose or other method until irrigation system is in operation. Do not let plants wilt.
- D. Soil Subsidence: Fill in as necessary soil subsidence that may occur because of settling or other processes. Replace mulch lost in areas of settling.
- E. Pruning: Prune, thin, and shape woody materials according to standard professional horticultural and arboricultural practices and in accordance with ANSI A300 (Part 1) Pruning.
1. Do not cut tree leaders. If multiple leaders are present, select the one that will best provide tree symmetry and remove the remainder. Trees with multiple leaders should have been rejected when delivered to the project site.
2. Remove only injured, dying, or dead branches from trees and shrubs. Prune to retain plant's natural character. Do not over prune plants. Pruning shall be done with clean, sharp tools.
3. Do not shear plant material. Allow plants to grow and develop their natural shape.
4. Prune lower branches of canopy trees, if necessary, to provide a 4 foot clear trunk.
- F. Pesticide and Herbicide Application
1. All planting areas shall be kept reasonable weed free during the entire maintenance period.
2. Application of any chemicals to control pest and weed growth in the planting areas shall be kept to a minimum. Use manual method or non-chemical products for weed removal whenever possible.
3. Apply chemical products according to requirements of authorities having jurisdiction and to manufacturer's written recommendations. Use only licensed applicators for the type of chemicals to be used. Many organic based products do not require a licensed applicator.
4. Coordinate chemical applications with Owner's operations and others in proximity to the work. Notify Owner before each application is performed.
- G. Protect plants from damage due to landscape operations and operations of other contractors and trades. Maintain protection during installation and maintenance periods. Treat, repair, or replace damaged plantings without additional cost to the Owner.
- H. Maintenance Data: Recommended procedures to be established by Owner for maintenance of all planting during a calendar year. Submit in written form at end of maintenance period.
- 3.14 MAINTENANCE BY OWNER DURING THE CONTRACTOR WARRANTY PERIOD**
- A. This condition applies when the Contractor is only contracted to provide maintenance for a period of less than the 1 year plant Warranty Period.
- B. The Contractor shall make periodic site visits to observe the Owner's maintenance and alert the Owner of any problems associated with their maintenance and to request changes.
- C. Notify the Owner in writing if maintenance, including watering, is not sufficient to maintain plants in a healthy condition. Describe maintenance deficiency and provide a solution. Notification must be made in a timely manner so that corrective action may be taken prior to the End of Warranty Acceptance date.
- D. Failure of the Contractor to make site visits and notify the Owner of maintenance deficiencies shall not be used as grounds for voiding or modifying the provisions of the plant Warranty.
- 3.15 CLEAN UP**
- A. During the course of construction, Contractor shall keep work areas clean at all times.
- B. Perform cleanup work upon completion of plant installation work and prior to Substantial Completion inspection.
1. Haul off all excavated materials, debris, excess soil material, and trash.
2. Sweep or wash off all pavement and roadways. Remove soil from all surfaces.
- C. Repair all damages caused to project site, adjacent property, structures, irrigation system, or existing plant material during installation work. Fill in all tire ruts in planting areas.
- D. Remove any erosion control (SWPPP) measures installed after grass has established.
- 3.16 PROJECT INSPECTION FOR SUBSTANTIAL AND FINAL COMPLETION**
- A. The Contractor shall request a Substantial Completion review from the Owner once work is sufficiently complete. During the Substantial Completion review, a punch list will be generated by the Landscape Architect. Once the punch list items are completed, Contractor shall request a Final Completion review.
- 3.17 FINAL ACCEPTANCE AFTER CONTRACTED MAINTENANCE PERIOD**
- A. Final acceptance will be given by the Owner or Landscape Architect once the contracted maintenance period expires.
- B. All work must be in acceptable condition. If not, Contractor shall provide corrective measures to the Owner's satisfaction.
- C. Once Final Acceptance is given, the Owner will assume maintenance of the project. Contractor shall provide Owner with the maintenance procedures for a calendar year in written format.
- 3.18 END OF 1 YEAR WARRANTY ACCEPTANCE**
- A. At the end of the Warranty period, the Owner or Landscape Architect shall observe all warranted work, upon written request of the Contractor. The request shall be received at least 4 calendar days before the anticipated date for observation.
- B. Acceptance of End of Warranty will be given if it is determined that all requirements of the Contract Documents have been met.
- END OF SECTION**



EAL



PROJECT NAME

BANDERA RETAIL CENTER
7706 BANDERA ROAD
SAN ANTONIO, TX 78238

PROJECT INFO.

PROJECT NUMBER: 201803

RAWN BY: ISP

CHECKED BY: ISP

SUE DATE

4-16-2018

REVISIONS

[illegible]

SHEET TITLE

SPECIFICATIONS

SHEET NUMBER

City of San Antonio Building Review Detail

Report Date: 10/05/2018 11:02 AM Submitted By: JOHNNY Page 1

Act # 1354470 A/P # 2368200 Act Type TRAFFIC TRAFFIC REVIEW # 3

Property Information
Address 7706 BANDERA RD
SAN ANTONIO TX 78240-0000
Location

Application Information
Type COMBLOGENCOMMERCIAL SINGLE BUILDING Priority SITE Type of Work NEW Dept of Commerce/COMMER
Square Footage 1,00 Declared Valuation 413000.00 A/P Name BANDERA RETAIL CENTER
Desc of Work SITE WORK ONLY FOR A GENERAL RETAIL BUILDING OF APPROXIMATELY 10,000 SQ. FT. WITH ASSOCIATED PARKING.
PROPERTY ZONED C-3. SEE GIS ZONING MAP IN OLE plan does not show sewer line.
9/18/18 LANDSCAPE / IRRIGATION REVIEWS DELETED. REVISIONS WILL BE SUBMITTED TO R LOYD. REVIEWER ERROR IN INITIAL LANDSCAPE REVIEW.
RETAINING WALLS UNDER 4 FEET WITH A SURCHARGE REQUIRE PERMIT AND CITY FINAL INSPECTION
SITE WORK ONLY. NO VERTICAL CONSTRUCTION

Initial Review
Issued Date/Time 10/02/2018 14:32 Issued By RG25545 System Generated
Scheduled Date/Time Department DSDENG Assigned To JA10726
Review Results
Reviewed By JA10726 Approved
Start Date/Time 10/04/2018 16:17 Completed Date/Time 10/04/2018 16:55 Suspense Date 10/07/2018 Actual Time 1.00

Comments
No Comments

Problems
Violation OTHER Description OTHER TYPE OF VIOLATION
Recorded Date 10/04/2018 00:00 Recorded By JA10726 Recorded Version 3
Resolved Date Resolved By Resolved Version
Status
Comments 10.04.18
RETAIL: 10,000 SQ. FT. MIN 1/300 MAX 1/200
REQUIRED MIN. 35 MAX. 50
PROVIDED MIN. 47 SPACES
REQUIRED BICYCLE SPACE: 3
PROVIDED BICYCLE SPACE: 5 (U RACK)
APPROACHES: EXISTING (BANDERA RD. TXDOT R.O.W. & WESTCHASE)
NOTE: A 25' INGRESS/EGRESS EASEMENT HAS BEEN PROVIDED ON PLAT # 080296.

TRAFFIC COMMENTS:
***Call city construction inspector at 210.207.1111, Option 0 prior to commencing any work or pouring concrete.
***Refer to sheet C1.0 dated and signed by the Engineer on (date here) for site layout.
***Dial (210) 207-1111 to schedule inspections twenty four (24) hours prior to pouring concrete flatwork and / or traffic (parking) inspections.
***PRIOR TO COMMENCING WORK IN CITY R.O.W. OBTAIN A LANE AND/OR A SIDEWALK CLOSURE PERMIT FROM PUBLIC WORKS-TRAFFIC ENGINEERING. CONTACT JOHN RODRIGUEZ AT 210.207.7755. ONCE PERMIT IS OBTAINED, PROVIDE A PROPER LANE CLOSURE WHICH IS TO BE SET UP BY A CERTIFIED BARRICADING COMPANY. IF THESE TWO ITEMS ARE NOT ACCOMPLISHED, A "STOP WORK ORDER" VIOLATION WILL BE ISSUED AND WORK CAN NOT COMMENCE UNTIL THE TWO ITEMS HAVE BEEN ADDRESSED ***
TEMPORARY CONSTRUCTION ACCESS DRIVES CONTACT ROW MANAGEMENT AT 210.207.7755 FOR A PERMIT TO WORK IN THE ROW
***All access driveways shall be provided with Clear Vision Area in accordance with UDC 35-506 (d) (5). Clear vision areas must be free of visual obstructions, e.g. structures, walls, fences and vegetation which are higher than three (3) feet and lower than eight (8) feet above the street pavement.
***Impervious cover shall be maintained or constructed as per UDC Section 35-526 (f) (1). Off-street parking, as per UDC Section 35-526 (f) (2) (f) (1) - Off-street parking facilities shall be constructed, maintained and operated in accordance with the following specifications: (1) Drainage and Surfacing. Areas shall be properly graded for drainage, surfaced with concrete, asphaltic concrete, or asphalt and maintained in good condition free of weeds, dust, trash and debris.
***City approved plans shall be maintained at the jobsite and be accessible to City inspectors at all times during work activities.
***All concrete work shall comply with COSA Standards and Specifications.
BE ADVISED THAT UTILITY RELOCATIONS MAY BE REQUIRED BY THIS SCOPE OF WORK - IF STREETLIGHTS MUST BE RELOCATED BECAUSE OF THIS MODIFICATION, PLEASE CONTACT ROGER ALMAGUER WITH DSD EARLY ON IN THE PROCESS TO REQUEST THE STREETLIGHT RELOCATIONS BY OPS ENERGY, OTHERWISE CONSTRUCTION TIMELINES MAY INCUR DELAYS BY AS MUCH AS 6-9 MONTHS. SEE ROGER'S CONTACT INFORMATION BELOW.
Roger Almaguer@SanAntonio.gov
Office: (210) 207-8075

CITY OF SAN ANTONIO
DEVELOPMENT SERVICES DEPARTMENT
PLANS REVIEW DIVISION
REVIEWED FOR CODE COMPLIANCE

TRADE	PLANS EXAMINER	DATE
BUILDING:	SM	9/18/18
FIRE:	CP	9/12/18
MECHANICAL:		
ELECTRICAL:	Wazhin	5-18-18
PLUMBING:		
TRAFFIC/SIDEWALK:	John	4/4/18
DRAINAGE:		
LANDSCAPE/IRRIGATION:	BE	10/1/18
TREE:	BE	10/1/18
HEALTH:		
HISTORICAL:		
SAWS:		
DISABILITY:		

THIS SET OF PLANS AND SPECIFICATIONS **MUST** BE KEPT ON THE JOB AT ALL TIMES. OTHERWISE THE JOB IS SUBJECT TO REJECTION IT IS UNLAWFUL TO MAKE ANY CHANGES OR ALTERATIONS ON SAME WITHOUT WRITTEN PERMISSION FROM THE BUILDING INSPECTOR'S OFFICE. CITY OF SAN ANTONIO
THE STAMPING OF THIS PLAN AND SPECIFICATIONS SHALL NOT BE HELD TO PERMIT OR TO BE APPROVAL OF THE VIOLATION OF ANY PROVISIONS OF ANY CITY ORDINANCE OR STATE LAW.

CITY OF SAN ANTONIO
DEVELOPMENT SERVICES DEPARTMENT
PLANS REVIEW DIVISION
REVIEWED FOR CODE COMPLIANCE

DATE: 10.12.18
BY: CD

City of San Antonio Building Review Detail

Report Date: 10/05/2018 11:02 AM Submitted By: JOHNNY Page 1

Act # 1354471 A/P # 2368200 Act Type SIDEWALK SIDEWALK REVIEW # 3

Property Information
Address 7706 BANDERA RD
SAN ANTONIO TX 78240-0000
Location

Application Information
Type COMBLOGENCOMMERCIAL SINGLE BUILDING Priority SITE Type of Work NEW Dept of Commerce/COMMER
Square Footage 1,00 Declared Valuation 413000.00 A/P Name BANDERA RETAIL CENTER
Desc of Work SITE WORK ONLY FOR A GENERAL RETAIL BUILDING OF APPROXIMATELY 10,000 SQ. FT. WITH ASSOCIATED PARKING.
PROPERTY ZONED C-3. SEE GIS ZONING MAP IN OLE plan does not show sewer line.
9/18/18 LANDSCAPE / IRRIGATION REVIEWS DELETED. REVISIONS WILL BE SUBMITTED TO R LOYD. REVIEWER ERROR IN INITIAL LANDSCAPE REVIEW.
RETAINING WALLS UNDER 4 FEET WITH A SURCHARGE REQUIRE PERMIT AND CITY FINAL INSPECTION
SITE WORK ONLY. NO VERTICAL CONSTRUCTION

Initial Review
Issued Date/Time 10/02/2018 14:32 Issued By RG25545 System Generated
Scheduled Date/Time Department DSDENG Assigned To JA10726
Review Results
Reviewed By JA10726 Approved
Start Date/Time 10/04/2018 16:17 Completed Date/Time 10/04/2018 16:55 Suspense Date 10/07/2018 Actual Time 1.00

Comments
No Comments

Problems
Violation OTHER Description OTHER TYPE OF VIOLATION
Recorded Date 10/04/2018 00:00 Recorded By JA10726 Recorded Version 3
Resolved Date Resolved By Resolved Version
Status
Comments 10.04.18
SITE IS PROPOSING NEW 6'-0" SIDEWALK (210' L.F. / 1,260 SQ. FT.) ALONG WESTCHASE. EXISTING CUEB TO REMAIN IF TO CURRENT CITY STANDARDS.
SITE IS PROPOSING NEW 10'-0" MULTI-USE PATH SIDEWALK ALONG BANDERA RD. (SH 16 TXDOT R.O.W.)

SIDEWALK COMMENTS:
Shall obtain approval/permits from TXDOT for any construction on State Right-Of-Way.
Engineer shall ensure that all existing/proposed sidewalk, approaches, and curbs comply with Texas Accessibility Standards and the UDC. Non-compliant concrete flatwork shall be replaced - wheelchair ramps shall comply with Public Works Wheelchair Ramp Details 2006 (truncated domes are required at controlled street intersections).
Wheel chair ramps at driveway approach(es) shall be broom finished (scoring, truncated domes or grooves are not permitted).
A sidewalk drain box will be required if there is surface water runoff over the sidewalk. All metal parts shall be galvanized.
As per UDC Section 35-506 (a) (2) sidewalks shall be constructed to current City and TAS Specs.
Note to Contractor: Any damage to existing pavement, curb or sidewalk must be repaired prior to Final Traffic Inspection.

RETAINING WALL UNDER 4 FEET W/ SURCHARGE = PERMIT & FINAL INSPECTION. SITE WORK ONLY. NO VERTICAL CONSTRUCTION.

Wazhin 5-18-18 Approved for site only